

公 告 第 3 0 - 1 号

令和 8 年 1 0 月 6 日

入 札 変 更 公 告

分任契約担当官

陸上自衛隊富山駐屯地

第 3 3 6 会計隊富山派遣隊長 野村 尚平

公告第 3 0 号「富山（8）駐屯地構内道路舗装等工事」に係る入札公告の一部を
下記のとおり変更するので、関係事項を承知のうえ参加されたい。

変更内容

入札公告のうち「数量計算書」を別添のとおり変更する。

問い合わせ先

〒 9 3 9 - 1 3 3 8 富山県砺波市鷹栖出 9 3 5 陸上自衛隊富山駐屯地

第 3 3 6 会計隊富山派遣隊 担当：野村

TEL 0 7 6 3 - 3 3 - 2 3 9 2（内線 3 4 5）

FAX 0 7 6 3 - 3 3 - 2 3 9 2

数量計算書

	名 称	規格・寸法	数量	単位	計算根拠										備考		
I	土木工事																
1	路面切削工																
①	舗装版切断	アスファルト舗装版15cm以下 無	193.0	m	(	57	+	8	)	m	×	2	=	130	m ²	隊舎表側	図番3/3
					(	15	+	8	)	m	×	2	=	46	m ²	隊舎裏側	
					(	0.5	+	8	)	m	×	2	=	17	m ²	隊舎西側	
					計									193	m ²	箇所あたり	
					合計					193	m ²	×	1	箇所	=	193	
②	殻運搬	舗装版破砕	38.6	m	(	57	+	8	)	m	×	2	=	130	m ²	隊舎表側	図番3/3
					(	15	+	8	)	m	×	2	=	46	m ²	隊舎裏側	
					(	0.5	+	8	)	m	×	2	=	17	m ²	隊舎西側	
					計									193	m ²	箇所あたり	
										193	m ²	×	0.2	m	=	38.6	
					合計					38.6	m ²	×	1	箇所	=	38.6	m ²
③	掘削	土砂	701.0	m ²	39	m	×	17	m				=	663	m ²	隊舎表側	図番3/3
					5	m	×	10	m				=	50	m ²	隊舎裏側	
					6	m	×	4	m	÷	2		=	12	m ²	隊舎裏側	
					計									701	m ²	箇所あたり	
					合計					701	m ²	×	1	箇所	=	701	
④	土砂等運搬	土砂、小規模	701.0	m ²	39	m	×	17	m				=	663	m ²	隊舎表側	図番3/3
					5	m	×	10	m				=	50	m ²	隊舎裏側	
					6	m	×	4	m	÷	2		=	12	m ²	隊舎裏側	
					計									701	m ²	箇所あたり	
					合計					701	m ²	×	1	箇所	=	701	
⑤	埋戻し	最大埋戻幅1m以上4m未満	701.0	m ²	39	m	×	17	m				=	663	m ²	隊舎表側	図番3/3
					5	m	×	10	m				=	50	m ²	隊舎裏側	
					6	m	×	4	m	÷	2		=	12	m ²	隊舎裏側	
					計									701	m ²	箇所あたり	
					合計					701	m ²	×	1	箇所	=	701	
⑥	不陸整正		701.0	m ²	39	m	×	17	m				=	663	m ²	隊舎表側	図番3/3
					5	m	×	10	m				=	50	m ²	隊舎裏側	
					6	m	×	4	m	÷	2		=	12	m ²	隊舎裏側	
					計									701	m ²	箇所あたり	
					合計					701	m ²	×	1	箇所	=	701	

数量計算書

名 称		規格・寸法	数量	単位	計算根拠										備考					
⑦	タンバ締固め		701.0	㎡	合計 701 ㎡ × 1 箇所 = 701 ㎡										図番3/3					
					39	m	×	17	m		=	663	㎡	隊舎表側						
					5	m	×	10	m		=	50	㎡	隊舎裏側						
					6	m	×	4	m	÷	2	=	12	㎡		隊舎裏側				
					計								701	㎡		箇所あたり				
⑧	下層路盤		701.0	㎡	合計 701 ㎡ × 1 箇所 = 701 ㎡										図番3/3					
					39	m	×	17	m		=	663	㎡	隊舎表側						
					5	m	×	10	m		=	50	㎡	隊舎裏側						
					6	m	×	4	m	÷	2	=	12	㎡		隊舎裏側				
					計								701	㎡		箇所あたり				
⑨	上層路盤（車道・路肩部）	再生粒度調整砕石 RM-40	701.0	㎡	合計 701 ㎡ × 1 箇所 = 701 ㎡										図番3/3					
					39	m	×	17	m		=	663	㎡	隊舎表側						
					5	m	×	10	m		=	50	㎡	隊舎裏側						
					6	m	×	4	m	÷	2	=	12	㎡		隊舎裏側				
					計								701	㎡		箇所あたり				
2 ①	舗装工事 表層（車道・路肩部）		701.0	㎡	合計 701 ㎡ × 1 箇所 = 701 ㎡										図番3/3					
					39	m	×	17	m		=	663	㎡	隊舎表側						
					5	m	×	10	m		=	50	㎡	隊舎裏側						
					6	m	×	4	m	÷	2	=	12	㎡		隊舎裏側				
					計								701	㎡		箇所あたり				
3 ①	水路工事 コンクリートはつり	3cm以下	6.0	㎡	合計 6 ㎡ × 1 箇所 = 6 ㎡															
					3	m	×	2	m		=	6	㎡	合棟隊舎裏側						
					計								6	㎡		箇所あたり				
					合計								6	㎡		×	1 箇所	=	6	㎡
					合計								6	㎡		×	1 箇所	=	6	㎡
②	現場打ち集水桝・街渠桝（本体）		1.0	基	計 1 基															
					合計 1 基 × 1 箇所 = 1 基															
					合計 1 基 × 1 箇所 = 1 基															
4	区画線設置																			

数 量 計 算 書

名 称		規格・寸法	数量	単位	計算根拠										備考		
①	区画線工	溶融式(手動)15cm 実線 白	4.6	㎡	30.8	m	×	0.15	m			=	4.62	㎡	図のとおり	図番3/3	
					合計								<u>4.62</u>	㎡	箇所あたり		
②	区画線工	ペイント式(車載)15cm 実線 橙	65.5	㎡	436.6	m	×	0.15	m			=	65.49	㎡	図のとおり	図番3/3	
					合計					65.49	㎡	×	1	箇所	=		<u>65.49</u>
③	区画線工	ペイント式(車載)14cm 実線 橙	2.8	㎡	20	m	×	0.14	m			=	2.8	㎡	図のとおり	図番3/3	
					合計					2.8	㎡	×	1	箇所	=		<u>2.8</u>
④	区画線工	ペイント式(車載)10cm 実線 橙	4.8	㎡	48.2	m	×	0.1	m			=	4.82	㎡	図のとおり	図番3/3	
					合計					4.82	㎡	×	1	箇所	=		<u>4.82</u>
⑤	区画線工	文字実線	22.1	㎡	4.9	m	×	1.5	m			=	7.35	㎡	図のとおり	図番3/3	
					合計					7.35	㎡	×	3	箇所	=		<u>22.05</u>
IV	その他工事																
1	産業廃棄物収集運搬処分																
①	産業廃棄物収集運搬処分	がれき類	701.0	㎡	39	m	×	17	m			=	663	㎡	隊舎表側	図番3/3	
					5	m	×	10	m			=	50	㎡	隊舎裏側		
					6	m	×	4	m	÷	2		=	12	㎡		隊舎裏側
					計									701	㎡		箇所あたり
					合計					701	㎡	×	1	箇所	=		<u>701</u>