



数量算出書(建築)

名 称	摘要	拾											小計	合計	単位	改め計		
撤去工事																		
床 コンクリートカッター切	t=150	m	0.85	+	1.07	+	0.85	+	1.07	=	3.84			3.84	3.84	m	3.8	
床 コンクリート撤去	t=150	m2	0.85	x	1.07			=	0.91					0.91	0.91	m2	0.9	
床 タイル撤去	25角 下地モルタル共	m2	3.64	x	1.38			=	5.02					5.02	5.02	m2	5.0	
ポリスチレンフィルム撤去	t=0.15	m2	0.85	x	1.07			=	0.91					0.91	0.91	m2	0.9	
碎石撤去	t=100	m2	0.85	x	1.07			=	0.91					0.91	0.91	m2	0.9	
天井 シーリング石膏ボード撤去	アスベスト含有建材 t=9.5 区画養生、湿潤養生共 床壁:区画養生(30.1m2)	m2	0.60	x	0.60			=	0.36					0.36	0.36	m2	0.4	
消耗品	防塵マスク(レベル3対応) 作業服、手袋 1セット分	式	1.00					=	1.00					1.00	1.00	式	1.0	
和風便器撤去	タンク共	カ所	1.00					=	1.00					1.00	1.00	カ所	1.0	
トイレブース撤去	W1040、H1900、t40 隔板W950...1カ所	カ所	1.00					=	1.00					1.00	1.00	カ所	1.0	
70.便所																		
塗装工事																		
天井 EP-G塗	石膏ボード面 B種	m2	0.60	x	0.60			=	0.36					0.36				
			0.60	x	0.60			=	0.36					0.36	0.72	m2	0.7	
内装工事																		
天井 シーリング石膏ボード	t=9.5	m2	0.60	x	0.60			=	0.36					0.36				
			0.60	x	0.60			=	0.36					0.36	0.72	m2	0.7	
撤去工事																		
天井 シーリング石膏ボード撤去	アスベスト含有建材 t=9.5 区画養生、湿潤養生共 床壁:区画養生(59.8m2)	m2	0.60	x	0.60			=	0.36					0.36				
			0.60	x	0.60			=	0.36					0.36	0.72	m2	0.7	
消耗品	防塵マスク(レベル3対応) 作業服、手袋 2セット分	式	1.00					=	1.00					1.00	1.00	式	1.0	
123隊舎 1階																		

数量算出書(建築)

名 称	摘要	拾										小計	合計	単位	改め計	
<b>金属工事</b>																
軽量鉄骨天井下地	19型 直張	m2	0.91	x	1.82			=	1.66					1.66		
			0.91	x	1.82			=	1.66					1.66	3.31	m2 3.3
<b>塗装工事</b>																
天井 EP-G塗	石膏ボード面 B種	m2	0.91	x	1.82			=	1.66					1.66		
			0.91	x	1.82			=	1.66					1.66	3.31	m2 3.3
<b>内装工事</b>																
天井 シーリング石膏ボード	t=9.5	m2	0.91	x	1.82			=	1.66					1.66		
			0.91	x	1.82			=	1.66					1.66	3.31	m2 3.3
<b>撤去工事</b>																
天井 シーリング石膏ボード撤去	アスベスト含有建材	m2	0.91	x	1.82			=	1.66					1.66		
	t=9.5 区画養生、湿潤養生共		0.91	x	1.82			=	1.66					1.66	3.31	m2 3.3
	床壁・区画養生(88.5m2)															
<b>消耗品</b>																
	防塵マスク(レベル3対応)	式	1.00					=	1.00					1.00	1.00	式 1.0
	作業服、手袋															
	1セット分															
軽量鉄骨天井下地撤去	LGS 野縁まで	m2	0.91	x	1.82			=	1.66					1.66		
			0.91	x	1.82			=	1.66					1.66	3.31	m2 3.3
<b>123隊舎 2階</b>																
<b>タイル工事</b>																
床 タイル	既存類似品 50角	m2	3.70	x	1.30			=	4.81					4.81		
			5.80	x	3.40			=	19.72					19.72		
			2.90	x	2.27			=	6.58					6.58		
		間仕切り壁	-1.35	x	-0.15	x	-2.00	=	-0.41					-0.41		
		間仕切り壁	-0.50	x	2.30			=	-1.15					-1.15	29.56	m2 29.6
<b>金属工事</b>																
軽量鉄骨天井下地	19型 直張	m2	0.91	x	1.82	x	2.00	=	3.31					3.31		
			0.91	x	0.91			=	0.83					0.83	4.14	m2 4.2
<b>左官工事</b>																
床 タイル下モルタル		m2	3.70	x	1.30			=	4.81					4.81		
			5.80	x	3.40			=	19.72					19.72		
			2.90	x	2.27			=	6.58					6.58		
		間仕切り壁	-1.35	x	-0.15	x	-2.00	=	-0.41					-0.41		
		間仕切り壁	-0.50	x	2.30			=	-1.15					-1.15	29.56	m2 29.6
<b>建具工事</b>																
TB-2		カ所	1.00					=	1.00					1.00	1.00	カ所 1.0

数量算出書(建築)

名称	摘要	拾															小計	合計	単位	改め計	
TB-3		カ所	1.00						=	1.00								1.00	1.00	カ所	1.0
塗装工事																					
天井 EP-G塗	石膏ボード面 B種	m2	0.91	x	1.82	x	2.00	=	3.31									3.31			
			0.60	x	0.60			=	0.36									0.36			
			0.91	x	0.91			=	0.83									0.83	4.50	m2	4.5
壁 EP-G塗	B種	m2	3.70	+	1.30	+	1.05	+	5.67	+	2.90	+	2.27	+	2.90	+					
			3.40	+	1.05	+	1.30	=	25.54									25.54			
			25.54	x	2.40			=	61.30									61.30			
	窓		-3.30	x	-1.50			=	-4.95									-4.95			
	片開戸		-0.60	x	-1.50	x	2.00	=	-1.80									-1.80			
	片開戸		-0.90	x	-2.00			=	-1.80									-1.80	78.29	m2	78.3
内装工事																					
天井 シージング石膏ボード	t=9.5	m2	0.91	x	1.82	x	2.00	=	3.31									3.31			
			0.60	x	0.60			=	0.36									0.36			
			0.91	x	0.91			=	0.83									0.83	4.50	m2	4.5
天井 化粧石膏ボード	t=9.5	m2	0.60	x	0.60			=	0.36									0.36			
			0.60	x	0.60			=	0.36									0.36	0.72	m2	0.7
ユニット及びその他工事																					
和式便器塞ぎ	0.7*0.4	カ所	4.00					=	4.00									4.00	4.00	カ所	4.0
L字ステンレス製見切り	L=80×80×3	m	3.15	+	0.21	+	0.21	=	3.57									3.15			
			3.29	+	0.21			=	3.50									3.29	6.44	m	6.4
撤去工事																					
床 コンクリートカッター切	t=150	m	0.70	+	0.40	+	0.70	+	0.40	=	2.20										
			2.20	x	4.00			=	8.80									8.80	8.80	m	8.8
床 コンクリート撤去	t=150 700*400	カ所	4.00					=	4.00									4.00	4.00	カ所	4.0
床 タイル撤去	50角 下地モルタル共	m2	3.70	x	1.30			=	4.81									4.81			
			5.80	x	3.40			=	19.72									19.72			
			2.90	x	2.28			=	6.61									6.61			
	間仕切り壁		-1.35	x	-0.15	x	-2.00	=	-0.41									-0.41			
	間仕切り壁		-0.50	x	2.30			=	-1.15									-1.15	29.59	m2	29.6
天井 シージング石膏ボード撤去	アスベスト含有建材	m2	0.91	x	1.82	x	2.00	=	3.31									3.31			
	t=9.5 区画養生、湿潤養生共		0.60	x	0.60			=	0.36									0.36			
	床壁、区画養生(120m2)		0.91	x	0.91			=	0.83									0.83	4.50	m2	4.5

数量算出書(建築)

名 称	摘要	拾										小計	合計	単位	改め計		
消耗品	防塵マスク(レベル3対応)	式	1.00											1.00	1.00	式	1.0
	作業服、手袋																
	1セット分																
天井 化粧石膏ボード撤	アスベスト含有建材	m2	0.60	x	0.60									0.36			
	t=9.5 区画養生、湿潤養生共		0.60	x	0.60									0.36	0.72	m2	0.7
	床壁、区画養生(51.8m2)																
消耗品	防塵マスク(レベル3対応)	式	1.00											1.00	1.00	式	1.0
	作業服、手袋																
	1セット分																
軽量鉄骨天井下地撤去	LGS 野縁まで	m2	0.91	x	1.82	x	2.00	=	3.31					3.31			
			0.91	x	0.91			=	0.83					0.83	4.14	m2	4.2
和風便器撤去		カ所	4.00					=	4.00					4.00	4.00	カ所	4.0
トイレブース撤去	W3110、H1900、t40	カ所	1.00					=	1.00					1.00	1.00	カ所	1.0
	隔板W1200…2カ所																
	隔板W1100…1カ所																
トイレブース撤去	W3245、H1900、t40	カ所	1.00					=	1.00					1.00	1.00	カ所	1.0
	隔板W1200…2カ所																
123階舎 3階																	
タイル工事																	
床 タイル	既存類似品 50角	m2	3.70	x	1.30			=	4.81					4.81			
			5.80	x	5.87			=	34.05					34.05			
	間仕切り壁		-1.35	x	-0.15	x	-2.00	=	-0.41					-0.41			
	間仕切り壁		-0.50	x	2.30			=	-1.15					-1.15	37.30	m2	37.3
左官工事		m2	3.70	x	1.30			=	4.81					4.81			
床 タイル下モルタル			5.80	x	5.87			=	34.05					34.05			
	間仕切り壁		-1.35	x	-0.15	x	-2.00	=	-0.41					-0.41			
	間仕切り壁		-0.50	x	2.30			=	-1.15					-1.15	37.30	m2	37.3
建具工事																	
TB-4		カ所	1.00					=	1.00					1.00	1.00	カ所	1.0
TB-5		カ所	1.00					=	1.00					1.00	1.00	カ所	1.0
塗装工事																	
天井 EP-G塗	石膏ボード面 B種	m2	0.60	x	0.60			=	0.36					0.36			
			0.60	x	0.60			=	0.36					0.36			
			0.60	x	0.60			=	0.36					0.36			

数量算出書(建築)

名 称	摘要	拾																小計	合計	単位	改め計
			0.60	x	0.60			=	0.36									0.36	1.44	m2	1.4
壁 EP-G塗	石膏ボード面 B種	m2	3.7	+	1.30	+	1.05	+	5.67	+	5.80	+	5.67	+	1.05	+		25.54			
			1.30					=	25.54									25.54			
			25.54	x	2.40			=	61.30									61.30			
	窓		-3.30	x	-1.50			=	-4.95									-4.95			
	片開戸		-0.60	x	-1.50	x	2.00	=	-1.80									-1.80			
	片開戸		-0.90	x	-2.00			=	-1.80									-1.80	78.29	m2	78.3
<b>内装工事</b>																					
天井 シーリング石膏ボード	t=9.5	m2	0.60	x	0.60			=	0.36									0.36			
			0.60	x	0.60			=	0.36									0.36			
			0.60	x	0.60			=	0.36									0.36			
			0.60	x	0.60			=	0.36									0.36	1.44	m2	1.4
<b>ユニット及びその他工事</b>																					
和式便器塞ぎ	0.7*0.4	カ所	8.00					=	8.00									8.00	8.00	カ所	8.0
L字ステンレス製見切り	L-80×80×3	m	5.50	+	0.22			=	5.72									5.50			
			5.50	+	0.21			=	5.71									5.50	11.00	m	11.0
<b>撤去工事</b>																					
床 コンクリートカッター切	t=150	m	0.70	+	0.40	+	0.70	+	0.40	=	2.20										
			2.20	x	8.00			=	17.60									17.60	17.60	m	17.6
床 コンクリート撤去	t=150 700*400	カ所	8.00					=	8.00									8.00	8.00	カ所	8.0
床 タイル撤去	50角 下地モルタル共	m2	3.70	x	1.30			=	4.81									4.81			
			5.80	x	5.68			=	32.94									32.94			
	間仕切り壁		-1.35	x	-0.15	x	-2.00	=	-0.41									-0.41			
	間仕切り壁		-0.50	x	2.30			=	-1.15									-1.15	36.20	m2	36.2
天井 シーリング石膏ボード撤去	アスベスト含有建材	m2	0.60	x	0.60			=	0.36									0.36			
	t=9.5 区画養生、湿潤養生共		0.60	x	0.60			=	0.36									0.36			
	床壁、区画養生(102m2)		0.60	x	0.60			=	0.36									0.36			
			0.60	x	0.60			=	0.36									0.36	1.44	m2	1.4
消耗品	防塵マスク(レベル3対応)	式	1.00					=	1.00									1.00	1.00	式	1.0
	作業服、手袋																				
	1セット分																				
天井 化粧石膏ボード撤去	アスベスト含有建材	m2	0.60	x	0.60			=	0.36									0.36			
	t=9.5 区画養生、湿潤養生共		0.60	x	0.60			=	0.36									0.36	0.72	m2	0.7
	床壁、区画養生(52m2)																				

数量算出書(建築)

名 称	摘要	拾														小計	合計	単位	改め計																	
消耗品	防塵マスク(レベル3対応)	式	1.00															=	1.00										1.00	1.00	式	1.0				
	作業服、手袋																																			
	1セット分																																			
和風便器撤去		カ所	8.00																													8.00	8.00	カ所	8.0	
トイレブース撤去	W5510、H1900、t40	カ所	2.00																													2.00	2.00	カ所	2.0	
	隔板W1200…4カ所																																			
172隊舎 1階																																				
地業工事																																				
土間 砕石地業	t=100 材工	m2	0.91	x	1.30																											=	1.18	1.18	m2	1.2
土間 ポリスチレンフィルム	t=0.15 材工	m2	0.91	x	1.30																											=	1.18	1.18	m2	1.2
コンクリート工事																																				
土間 コンクリート	Fc=21N S-15	m3	0.91	x	1.30	x	0.12																									=	0.14	0.14	m3	0.2
土間 コンクリート打設費	人力	m3	0.91	x	1.30	x	0.12																									=	0.14	0.14	m3	0.2
鉄筋工事																																				
土間 異形鉄筋	SD295A D-10	kg	0.91	÷	0.20	=	4.55	≒	5.00	x	0.91	=	4.55	x	0.56	=	2.55	2.55																		
			1.3	÷	0.20	=	6.50	≒	7.00	x	1.30	=	9.10	x	0.56	=	5.10	5.10	7.64	kg	7.64															
土間 異形加工組立	スベラー、運搬費共	kg	0.91	÷	0.20	=	4.55	≒	5.00	x	0.91	=	4.55	x	0.56	=	2.55	2.55																		
			1.3	÷	0.20	=	6.50	≒	7.00	x	1.30	=	9.10	x	0.56	=	5.10	5.10	7.64	kg	7.64															
土間 あと施工アンカー	D10(@200)	カ所	0.91	÷	0.20	=	4.55	≒	5.00																											
			1.3	÷	0.20	=	6.50	≒	7.00																											
タイル工事																																				
床 タイル	既存類似品 50角	m2	1.80	x	1.30																											=	2.34	2.34	m2	2.3
巾木 タイル	100x200	m	1.11	+	1.3	+	1.11																									=	3.52	3.52	m	3.5
左官工事																																				
床 タイル下モルタル		m2	1.80	x	1.30																											=	2.34	2.34	m2	2.3
巾木 タイル下モルタル		m	1.11	+	1.3	+	1.11																									=	3.52			
		m2	3.52	x	0.20																											=	0.70	0.70	m2	0.7
塗装工事																																				
壁 EP-G塗	B種	m2	1.80	*	1.30	*	1.80	*	1.30	=	6.20																									
			6.20	x	2.40																											=	14.88	14.88		



数量算出書(建築)

名 称	摘要	拾										小計	合計	単位	改め計			
		式	1.00															
消耗品	防塵マスク(レベル3対応)	式	1.00												1.00	1.00	式	1.0
	作業服、手袋																	
	1セット分																	
軽量鉄骨天井下地撤去	LGS 野縁まで	m2	0.91	x	0.91									0.83	0.83	m2	0.8	
175本部隊舎 2階																		
タイル工事																		
床 タイル	既存類似品 200角	m2	1.10	x	1.20									1.32	1.32	m2	1.3	
金属工事																		
軽量鉄骨天井	19型 直張	m2	0.91	x	0.91									0.83	0.83	m2	0.8	
左官工事																		
床 タイル下モルタル		m2	1.10	x	1.20									1.32	1.32	m2	1.3	
建具工事																		
TB-6		カ所	1.00											1.00	1.00	カ所	1.0	
塗装工事																		
天井 EP-G塗	石膏ボード面 B種	m2	0.91	x	0.91									0.83	0.83	m2	0.8	
内装工事																		
天井 シーリング石膏	t=9.5	m2	0.91	x	0.91									0.83	0.83	m2	0.8	
ユニット及びその他工事																		
和式便器塞ぎ	0.7*0.4	カ所	カ所	1.00										1.00	1.00	カ所	1.0	
撤去工事																		
床 コンクリートカッター切	t=150	m	0.70	+	0.40	+	0.70	+	0.40	=	2.20			2.20	2.20	m	2.2	
床 コンクリート撤去	t=150 700*400	カ所	1.00											1.00	1.00	カ所	1.0	
床 タイル撤去	200角 下地モルタル共	m2	1.10	x	1.20									1.32	1.32	m2	1.3	
天井 シーリング石膏ボード撤去	アスベスト含有建材	m2	0.91	x	0.91									0.83	0.83	m2	0.8	
	t=9.5 区画養生、溜溜養生共																	
	床壁・区画養生(70.5m2)																	
消耗品	防塵マスク(レベル3対応)	式	1.00											1.00	1.00	式	1.0	
	作業服、手袋																	
	1セット分																	
軽量鉄骨天井下地撤去	LGS 野縁まで	m2	0.91	x	0.91									0.83	0.83	m2	0.8	

数量算出書(建築)

名 称	摘要	拾										小計	合計	単位	改め計		
		カ所	1.00														
和風便器撤去		カ所	1.00					=	1.00					1.00	1.00	カ所	1.0
トイレブース撤去	W3500、H1900、t40	カ所	1.00					=	1.00					1.00	1.00	カ所	1.0
	隔板W1100…2カ所																
	隔板W900…1カ所																
175本部隊舎 3階																	
タイル工事																	
床 タイル	既存類似品 50角	m2	3.12	x	2.65			=	8.27					8.27	8.27	m2	8.3
左官工事																	
床 タイル下モルタル		m2	3.12	x	2.65			=	8.27					8.27	8.27	m2	8.3
建具工事																	
TB-7		カ所	1.00					=	1.00					1.00	1.00	カ所	1.0
塗装工事																	
壁 EP-G塗	B種	m2	2.65	+	2.65			=	5.30								
			5.30	x	2.40			=	12.72					12.72	12.72	m2	12.7
ユニット及びその他工事																	
和式便器塞ぎ	0.7*0.4	カ所	1.00					=	1.00					1.00	1.00	m2	1.0
撤去工事																	
床 コンクリートカッター切	t=150	m	0.70	+	0.40	+	0.70	+	0.40	=	2.20			2.20	2.20	m	2.2
床 コンクリート撤去	t=150 700*400	カ所	1.00					=	1.00					1.00	1.00	カ所	1.0
床 タイル撤去	50角 下地モルタル共	m2	3.12	x	2.65			=	8.27					8.27	8.27	m2	8.3
和風便器撤去	タンク共	カ所	1.00					=	1.00					1.00	1.00	カ所	1.0
トイレブース撤去	W2580、H1900、t40	カ所	1.00					=	1.00					1.00	1.00	カ所	1.0
	隔板W1300…1カ所																
	隔板W1100…1カ所																
195.需品整備工場 1階																	
地業工事																	
土間 砕石地業	t=100 材工	m2	1.20	x	2.00			=	2.40					2.40			
			1.20	x	0.80			=	0.96					0.96	3.36	m2	3.4
土間 ホリスチレンフィルム	t=0.15 材工	m2	1.20	x	2.00			=	2.40					2.40			
			1.20	x	0.80			=	0.96					0.96	3.36	m2	3.4
コンクリート工事																	

数量算出書(建築)

名 称	摘要	拾																小計	合計	単位	改め計
土間 コンクリート	Fc=21N S-15	m3	1.20	x	2.00	x	0.12	=	0.29									0.29			
			1.20	x	0.80	x	0.12	=	0.12										0.12	0.40	m3
土間 コンクリート打設費	人力	m3	1.20	x	2.00	x	0.12	=	0.29									0.29			
			1.20	x	0.80	x	0.12	=	0.12									0.12	0.40	m3	0.4
<b>鉄筋工事</b>																					
土間 異形鉄筋	SD295A D-10	kg	1.2	÷	0.20	=	6.00	≒	6.00	x	1.20	=	7.20	x	0.56	=	4.03	4.03			
			2.0	÷	0.20	=	10.00	≒	10.00	x	2.00	=	20.00	x	0.56	=	11.20	11.20			
			1.2	÷	0.20	=	6.00	≒	6.00	x	1.20	=	7.20	x	0.56	=	4.03	4.03			
			0.8	÷	0.20	=	4.00	≒	4.00	x	0.80	=	3.20	x	0.56	=	1.79	1.79	21.06	kg	21.06
土間 異形加工組立	スパーサー、運搬費共	kg	1.2	÷	0.20	=	6.00	≒	6.00	x	1.20	=	7.20	x	0.56	=	4.03	4.03			
			2.0	÷	0.20	=	10.00	≒	10.00	x	2.00	=	20.00	x	0.56	=	11.20	11.20			
			1.2	÷	0.20	=	6.00	≒	6.00	x	1.20	=	7.20	x	0.56	=	4.03	4.03			
			0.8	÷	0.20	=	4.00	≒	4.00	x	0.80	=	3.20	x	0.56	=	1.79	1.79	21.06	kg	21.06
土間 あと施工アンカー	D10(@200)	カ所	1.2	÷	0.20	=	6.00	≒	6.00								6.00				
			2.0	÷	0.20	=	10.00	≒	10.00								10.00				
			1.2	÷	0.20	=	6.00	≒	6.00								6.00				
			0.8	÷	0.20	=	4.00	≒	4.00								4.00	26.00	カ所	26.00	
<b>タイル工事</b>																					
床 タイル	既存類似品 25角	m2	3.60	x	2.00			=	7.20								7.20	7.20	m2	7.2	
壁タイル	既存類似品 75角	m2	0.88	+	1.20	+	0.88	=	2.96												
			2.96	x	0.37			=	1.10								1.10	1.10	m2	1.1	
<b>左官工事</b>																					
床 タイル下モルタル		m2	3.60	x	2.00			=	7.20								7.20	7.20	m2	7.2	
壁 タイル下モルタル		m2	0.88	+	1.20	+	0.88	=	2.96												
			2.96	x	0.37			=	1.10								1.10	1.10	m2	1.1	
<b>塗装工事</b>																					
天井 EP-G塗	石膏ボード面 B種	m2	0.91	x	0.91			=	0.83								0.83	0.83	m2	0.8	
<b>内装工事</b>																					
天井 シーリング	石t=9.5	m2	0.91	x	0.91			=	0.83								0.83	0.83	m2	0.8	
天井 化粧石膏	t=9.5	m2	0.60	x	0.60			=	0.36								0.36				
			0.60	x	0.60			=	0.36							0.36	0.72	m2	0.7		
<b>撤去工事</b>																					
床スラブ撤去	t120	m2	1.20	x	2.00			=	2.40								2.40				

数量算出書(建築)

名 称	摘要	拾										小計	合計	単位	改め計	
		m2	1.20	x	0.80	=	0.96	m2	1.20	x	0.18					=
												0.96				
												0.22	3.58	m2	3.6	
床 タイル撤去	25角 下地モルタル共	m2	3.60	x	2.00	=	7.20					7.20				
		m2	1.20	x	0.30	=	0.36					0.36	7.56	m2	7.6	
ホリスレンフィルム撤去	t=0.15	m2	1.20	x	0.80	=	0.96					0.96				
			1.20	x	2.00	=	2.40					2.40	3.36	m2	3.4	
碎石撤去	t=100	m2	1.20	x	0.80	=	0.96					0.96				
			1.20	x	2.00	=	2.40					2.40	3.36	m2	3.4	
壁タイル撤去	75角 下地モルタル共	m2	0.88	+	1.20	+	0.88	=	2.96							
		m2	2.96	x	0.08	=	0.24					0.24	0.24	m2	0.2	
天井 シーズン石膏ボード撤去	アスベスト含有建材 t=9.5 区画養生、湿潤養生共 床壁:区画養生(17.8m2)	m2	0.91	x	0.91	=	0.83					0.83	0.83	m2	0.8	
消耗品	防塵マスク(レベル3対応) 作業服、手袋 1セット分	式	1.00			=	1.00					1.00	1.00	式	1.0	
天井 化粧石膏ボード撤	アスベスト含有建材 t=9.5 区画養生、湿潤養生共 床壁:区画養生(90.6m2)	m2	0.60	x	0.60	=	0.36					0.36	0.72	m2	0.7	
消耗品	防塵マスク(レベル3対応) 作業服、手袋 1セット分	式	1.00			=	1.00					1.00	1.00	式	1.0	
和風便器撤去	タンク共	カ所	2.00			=	2.00					2.00	2.00	カ所	2.0	
201隊舎 4階 内装工事																
天井 化粧石膏ボード	t=9.5	m2	0.60	x	0.60	=	0.36					0.36	0.36	m2	0.4	
撤去工事																
天井 化粧石膏ボード撤	アスベスト含有建材 t=9.5 区画養生、湿潤養生共 床壁:区画養生(23.2m2)	m2	0.60	x	0.60	=	0.36					0.36	0.36	m2	0.4	
消耗品	防塵マスク(レベル3対応) 作業服、手袋 1セット分	式	1.00			=	1.00					1.00	1.00	式	1.0	

数量算出書(建築)

名 称	摘要	拾										小計	合計	単位	改め計	
204 体育館																
タイル工事																
床 タイル	既存類似品 50角	m2	3.30	x	4.20	=	13.86					13.86				
		m2	3.30	x	3.40	=	11.22					11.22	25.08	m2	25.1	
左官工事																
床 タイル下モルタル	既存類似品 50角	m2	3.30	x	4.20	=	13.86					13.86				
			3.30	x	3.40	=	11.22					11.22	25.08	m2	25.1	
建具工事																
トイレース 扉外開きに再	W=600 H=1900	カ所	2.00			=	2.00					2.00	2.00	カ所	2.0	
トイレース 再取付け	W3210、H=1900、t40	カ所	1.00			=	1.00					1.00	1.00	カ所	1.0	
	隔板W960…3カ所															
トイレース 再取付け	W3225、H=1900、t40	カ所	1.00			=	1.00					1.00	1.00	カ所	1.0	
	隔板W970…2カ所															
塗装工事																
天井 EP-G塗	石膏ボード面 B種	m2	0.60	x	0.60	=	0.36					0.36				
			0.60	x	0.60	=	0.36					0.36				
			0.60	x	0.60	=	0.36					0.36				
			0.60	x	0.60	=	0.36					0.36	1.44	m2	1.4	
壁 EP-G塗	B種	m2	3.30	+	4.20	+	3.30	+	4.20	=	15.00					
			15.00	x	2.40	=	36.00					36.00				
	片開きドア		-0.90	x	-2.00	=	-1.80					-1.80				
	窓		-1.60	x	-1.50	=	-2.40					-2.40	31.80	m2	31.8	
			3.00	+	3.40	+	3.00	+	3.40	=	12.80					
			12.80	x	2.40	=	30.72					30.72				
			-0.90	x	-2.00	=	-1.80					-1.80	28.92	m2	28.9	
														計	60.7	
内装工事																
天井 シーリング石膏	t=9.5	m2	0.60	x	0.60	=	0.36					0.36				
			0.60	x	0.60	=	0.36					0.36				
			0.60	x	0.60	=	0.36					0.36				
			0.60	x	0.60	=	0.36					0.36	1.44	m2	1.4	
天井 化粧石膏	t=9.5	m2	0.60	x	0.60	=	0.36					0.36				
			0.60	x	0.60	=	0.36					0.36	0.72	m2	0.7	
ユニット及びその他工事																
和式便器塞ぎ	0.7*0.4	カ所	3.00			=	3.00					3.00	3.00	カ所	3.0	
撤去工事																
床 コンクリートカッター切	t=150	m	0.70	+	0.40	+	0.70	+	0.40	=	2.20					

数量算出書(建築)

名 称	摘要	拾										小計	合計	単位	改め計	
			2.20	x	3.00			=	6.60				6.60	6.60	m	6.6
床 コンクリート撤去	t=150 700*400	カ所	3.00					=	3.00				3.00	3.00	カ所	3.0
床 タイル撤去	50角 下地モルタル共	m2	3.30	x	4.20			=	13.86				13.86			
			3.00	x	3.40			=	10.20				10.20	24.06	m2	24.1
天井 シーリング石膏ボード撤去	アスベスト含有建材	m2	0.60	x	0.60			=	0.36				0.36			
	t=9.5 区画養生、湿潤養生共		0.60	x	0.60			=	0.36				0.36			
	床壁:区画養生(93.6m2)		0.60	x	0.60			=	0.36				0.36			
			0.60	x	0.60			=	0.36				0.36	1.44	m2	1.4
消耗品	防塵マスク(レベル3対応) 作業服、手袋 2セット分	式	1.00					=	1.00				1.00	1.00	式	1.0
天井 化粧石膏ボード撤去	アスベスト含有建材	m2	0.60	x	0.60			=	0.36				0.36			
	t=9.5 区画養生、湿潤養生共		0.60	x	0.60			=	0.36				0.36	0.72	m2	0.7
	床壁:区画養生(66.2m2)															
消耗品	防塵マスク(レベル3対応) 作業服、手袋 2セット分	式	1.00					=	1.00				1.00	1.00	式	1.0
和風便器撤去		カ所	3.00					=	3.00				3.00	3.00	カ所	3.0
208 整備工場 1階																
タイル工事																
床 タイル	既存類似品 50角	m2	3.20	x	4.50			=	14.40				14.40	14.40	m2	14.4
左官工事																
床 タイル下モルタル		m2	3.20	x	4.50			=	14.40				14.40	14.40	m2	14.4
建具工事																
トイレアース再取付け	W3020、H=1900、t40 隔板W1000…1カ所 隔板W1380…2カ所 隔板W600…1カ所	カ所	1.00					=	1.00				1.00	1.00	カ所	1.0
塗装工事																
天井 EP-G塗	石膏ボード面 B種	m2	0.60	x	0.60			=	0.36				0.36			
			0.60	x	0.60			=	0.36				0.36	0.72	m2	0.7
壁 EP-G塗	B種	m2	3.20	+	4.50	+	3.20	+	4.50	=	15.40					
			15.40	x	2.50			=	38.50				38.50			
	窓		-1.65	*	-0.60			=	-0.99				-0.99			
	片開きドア		-0.90	*	-2.00			=	-1.80				-1.80	35.71	m2	35.7

数量算出書(建築)

名 称	摘要	拾											小計	合計	単位	改め計		
<b>内装工事</b>																		
天井 シーリング石	t=9.5	m2	0.60	x	0.60	=	0.36								0.36			
			0.60	x	0.60	=	0.36								0.36	0.72	m2	0.7
<b>ユニット及びその他工事</b>																		
和式便器塞ぎ	0.7*0.4	カ所	1.00			=	1.00								1.00	1.00	カ所	1.0
<b>撤去工事</b>																		
床 コンクリートカッター切	t=150	m	0.70	+	0.40	+	0.70	+	0.40	=	2.20				2.20	2.20	m	2.2
床 コンクリート撤去	t=150 700*400	カ所	1.00			=	1.00								1.00	1.00	カ所	1.0
床 タイル撤去	50角 下地モルタル共	m2	3.30	x	4.50	=	14.85								14.85	14.85	m2	14.9
天井 シーリング石膏ボード撤去	アスベスト含有建材	m2	0.60	x	0.60	=	0.36								0.36			
	t=9.5 区画養生、湿潤養生共		0.60	x	0.60	=	0.36								0.36	0.72	m2	0.7
	床壁:区画養生(94.4m2)																	
消耗品	防塵マスク(レベル3対応) 作業服、手袋 2セット分	式	1.00			=	1.00								1.00	1.00	式	1.0
和風便器撤去		カ所	1.00			=	1.00								1.00	1.00	カ所	1.0
<b>211. 医務室 1階</b>																		
<b>タイル工事</b>																		
床 タイル	既存類似品 50角	m2	2.90	x	3.00	=	8.70								8.70			
			2.10	x	2.10	=	4.41								4.41	13.11	m2	13.1
<b>左官工事</b>																		
床 タイル下モルタル		m2	2.90	x	3.00	=	8.70								8.70			
			2.10	x	2.10	=	4.41								4.41	13.11	m2	13.1
<b>建具工事</b>																		
TB-8		カ所	1.00			=	1.00								1.00	1.00	m2	1.0
<b>塗装工事</b>																		
天井 EP-G塗	石膏ボード面 B種	m2	0.60	x	0.60	=	0.36								0.36	0.36	m2	0.4
壁 EP-G塗	B種	m2	5.00	+	3.00	+	2.90	+	0.90	+	2.10	+	2.10	=	16.00			
			16.00	x	2.40	=	38.40								38.40			
	窓		-2.10	x	-0.60	=	-1.26								-1.26			





数量算出書(建築)

名称	摘要	拾										小計	合計	単位	改め計			
天井 EP-G塗	石膏ボード面 B種	m2	0.91	x	0.91			=	0.83						0.83			
			0.91	x	0.91			=	0.83						0.83	1.66	m2	1.7
壁 EP-G塗	B種		1.20	+	2.70	+	1.20	+	2.70	=	7.80							
		m2	7.80	x	2.40	x	2.00	=	15.60						15.60			
	窓		-0.80	x	-0.60	x	2.00	=	-0.96						-0.96			
	片開きドア		-0.90	x	-2.00	x	2.00	=	-3.60						-3.60	11.04	m2	11.0
<b>内装工事</b>																		
天井 シーリング石膏	t=9.5	m2	0.91	x	0.91			=	0.83						0.83			
			0.91	x	0.91			=	0.83						0.83	1.66	m2	1.7
<b>撤去工事</b>																		
土間スラブ撤去	t120	m2	2.40	x	2.70			=	6.48						6.48			
		m2	2.40	x	0.18			=	0.43						0.43	6.91	m2	6.9
床 タイル撤去	50角 下地モルタル共	m2	2.40	x	2.70			=	6.48						6.48			
	立上り		1.20	x	0.30			=	0.36						0.36	6.84	m2	6.8
巾木タイル撤去	100×200	m	1.03	+	1.2	+	1.03	=	3.26						3.26	3.26	m	3.3
ポリスチレンフィルム撤去	t=0.15	m2	2.40	x	2.70			=	6.48						6.48	6.48	m2	6.5
碎石撤去	t=100	m2	1.20	x	1.50			=	1.80						1.80			
			1.20	x	0.83			=	1.00						1.00	2.80	m2	2.8
天井 シーリング石膏ボード撤去	アスベスト含有建材	m2	0.91	x	0.91			=	0.83						0.83			
	t=9.5 区画養生、湿潤養生共		0.91	x	0.91			=	0.83						0.83	1.66	m2	1.7
	床壁:区画養生(43.9m2)																	
消耗品	防塵マスク(レベル3対応)	式	1.00					=	1.00						1.00	1.00	式	1.0
	作業服、手袋																	
	1セット分																	
天井 化粧石膏ボード撤去	アスベスト含有建材	m2	0.60	x	0.60			=	0.36						0.36	0.36	m2	0.4
	t=9.5 区画養生、湿潤養生共																	
	床壁:区画養生(35.5m2)																	
消耗品	防塵マスク(レベル3対応)	式	1.00					=	1.00						1.00	1.00	式	1.0
	作業服、手袋																	
	1セット分																	
和風便器撤去		方所	2.00					=	2.00						2.00	2.00	m2	2.0

数量算出書(建築)

名 称	摘要	拾																小計	合計	単位	改め計	
216. 給排水所 1階																						
地業工事																						
土間 砕石地業	t=100 材工	m2	1.30	x	0.83	=	1.08											1.08	1.08	m2	1.1	
土間 ホリスチレンフィルム	t=0.15 材工	m2	1.30	x	0.83	=	1.08											1.08	1.08	m2	1.1	
コンクリート工事																						
土間 コンクリート	Fe=21N S-15	m3	1.30	x	0.83	x	0.12	=	0.13									0.13	0.13	m3	0.1	
土間 コンクリート打設費	人力	m3	1.30	x	0.83	x	0.12	=	0.13									0.13	0.13	m3	0.1	
鉄筋工事																						
土間 異形鉄筋	SD295A D-10	kg	1.3	÷	0.20	=	6.50	≒	7.00	x	1.30	=	9.10	x	0.56	=	5.10	5.10				
			0.83	÷	0.20	=	4.15	≒	5.00	x	0.83	=	4.15	x	0.56	=	2.32	2.32	7.42	kg	7.42	
土間 異形加工組立	スパーサー、運搬費共	kg	1.3	÷	0.20	=	6.50	≒	7.00	x	1.30	=	9.10	x	0.56	=	5.10	5.10				
			0.83	÷	0.20	=	4.15	≒	5.00	x	0.83	=	4.15	x	0.56	=	2.32	2.32	7.42	kg	7.42	
土間 あと施工アンカー	D10(@200)	カ所	1.3	÷	0.20	=	6.50	≒	7.00									7.00				
			0.83	÷	0.20	=	4.15	≒	5.00									5.00	12.00	カ所	12.00	
タイル工事																						
床 タイル	既存類似品 50角	m2	1.30	x	2.00	=	2.60											2.60	2.60	m2	2.6	
巾木 タイル	100x200	m	0.83	+	1.2	+	0.83	=	2.86									2.86	2.86	m	2.9	
左官工事																						
床 タイル下モルタル	既存類似品 50角	m2	1.30	x	2.00	=	2.60											2.60	2.60	m2	2.6	
巾木 タイル下モルタル		m	0.83	+	1.2	+	0.83	=	2.86													
		m2	2.86	x	0.20	=	0.57											0.57	0.57	m2	0.6	
塗装工事																						
天井 EP-G塗	石膏ボード面 B種	m2	0.60	x	0.60	=	0.36											0.36	0.36	m2	0.4	
壁 EP-G塗	B種		1.30	+	2.00	+	1.30	+	2.00	=	6.60											
		m2	6.60	x	2.40	=	15.84											15.84				
	窓		-0.80	x	-0.80	=	-0.64											-0.64				
	片開きドア		-0.90	x	-2.00	=	-1.80											-1.80	13.40	m2	13.4	
内装工事																						
天井 シーリング石	t=9.5	m2	0.60	x	0.60	=	0.36											0.36	0.36	m2	0.4	
天井 化粧石膏	t=9.5	m2	0.60	x	0.60	=	0.36											0.36	0.36	m2	0.4	

数量算出書(建築)

名称	摘要	拾										小計	合計	単位	改め計	
<b>撤去工事</b>																
土間スラブ撤去	t120	m2	1.30	x	0.83			=	1.08			1.08				
		m2	1.30	x	0.18			=	0.23			0.23	1.31	m2	1.3	
床 タイル撤去	50角 下地モルタル共	m2	1.30	x	2.00			=	2.60			2.60				
	立上り		1.30	x	0.30			=	0.39			0.39	2.99	m2	3.0	
巾木タイル撤去	100×200	m	1.03	+	1.3	+	1.03	=	3.36			3.36	3.36	m	3.4	
ポリスチレンフィルム撤去	t=0.15	m2	1.30	x	0.83			=	1.08			1.08	1.08	m2	1.1	
碎石撤去	t=100	m2	1.30	x	0.83			=	1.08			1.08	1.08	m2	1.1	
天井 シーズンク石膏ボード撤去	アスベスト含有建材	m2	0.60	x	0.60			=	0.36			0.36	0.36	m2	0.4	
	t=9.5 区画養生、湿潤養生共															
	床壁・区画養生(18.4m2)															
消耗品	防護マスク(レベル3対応)	式	1.00					=	1.00			1.00	1.00	式	1.0	
	作業服、手袋															
	1セット分															
天井 化粧石膏ボード撤去	アスベスト含有建材	m2	0.60	x	0.60			=	0.36			0.36	0.36	m2	0.4	
	t=9.5 区画養生、湿潤養生共															
	床壁・区画養生(23.2m2)															
消耗品	防護マスク(レベル3対応)	式	1.00					=	1.00			1.00	1.00	式	1.0	
	作業服、手袋															
	1セット分															
和風便器撤去		カ所	1.00					=	1.00			1.00	1.00	カ所	1.0	
<b>217. 隊舎 5階</b>																
<b>塗装工事</b>																
天井 EP-G塗	石膏ボード面 B種	m2	0.60	x	0.60			=	0.36			0.36				
			0.60	x	0.60			=	0.36			0.36				
			0.60	x	0.60			=	0.36			0.36				
			0.60	x	0.60			=	0.36			0.36	1.44	m2	1.4	
壁 EP-G塗	B種		6.57	+	5.00	+	6.57	+	5.00	23.14						
		m2	23.14	x	2.40			=	55.54			55.54				
	片開きドア		-0.60	*	-1.50			=	-0.90			-0.90				



数量算出書(建築)

名 称	摘要	拾										い										小計	合計	単位	改め計													
<b>撤去工事</b>																																						
天井 シーリング石膏ボード撤去	アスベスト含有建材	m2	0.60	x	0.60				=	0.36								0.36																				
	t=9.5 区画養生、湿潤養生共		0.60	x	0.60				=	0.36								0.36																				
	床壁:区画養生(88.5m2)		0.60	x	0.60				=	0.36								0.36																				
			0.60	x	0.60				=	0.36								0.36	1.44	m2	1.4																	
消耗品	防塵マスク(レベル3対応) 作業服、手袋 1セット分	式	1.00						=	1.00								1.00	1.00	式	1.0																	
<b>天井 化粧石膏ボード撤去</b>																																						
天井 化粧石膏ボード撤去	アスベスト含有建材	m2	0.60	x	0.60				=	0.36								0.36	0.36	m2	0.4																	
	t=9.5 区画養生、湿潤養生共																																					
	床壁:区画養生(23.2m2)																																					
消耗品	防塵マスク(レベル3対応) 作業服、手袋 1セット分	式	1.00						=	1.00								1.00	1.00	式	1.0																	
<b>217. 隊舎 7階 塗装工事</b>																																						
天井 EP-G塗	石膏ボード面 B種	m2	0.60	x	0.60				=	0.36								0.36																				
			0.60	x	0.60				=	0.36								0.36																				
			0.60	x	0.60				=	0.36								0.36																				
			0.60	x	0.60				=	0.36								0.36	1.44	m2	1.4																	
壁 EP-G塗	B種		6.57	+	5.00	+	6.57	+	5.00	23.14																												
		m2	23.14	x	2.40				=	55.54								55.54																				
	片開きドア		-0.60	*	-1.50				=	-0.90								-0.90																				
	片開きドア		-0.90	*	-2.00				=	-1.80								-1.80	52.84	m2	52.8																	
<b>内装工事</b>																																						
天井 シーリング石膏ボード	t=9.5	m2	0.60	x	0.60				=	0.36								0.36																				
			0.60	x	0.60				=	0.36								0.36																				
			0.60	x	0.60				=	0.36								0.36																				
			0.60	x	0.60				=	0.36								0.36	1.44	m2	1.4																	
天井 化粧石膏ボード	t=9.5	m2	0.60	x	0.60				=	0.36								0.36	0.36	m2	0.4																	
<b>撤去工事</b>																																						
天井 シーリング石膏ボード撤去	アスベスト含有建材	m2	0.60	x	0.60				=	0.36								0.36																				
	t=9.5 区画養生、湿潤養生共		0.60	x	0.60				=	0.36								0.36																				
	床壁:区画養生(88.5m2)		0.60	x	0.60				=	0.36								0.36																				
			0.60	x	0.60				=	0.36								0.36	1.44	m2	1.4																	

数量算出書(建築)

名 称	摘要	拾										小計	合計	単位	改め計				
		式	1.00													=	1.00		
消耗品	防塵マスク(レベル3対応)	式	1.00													1.00	1.00	式	1.0
	作業服、手袋																		
	1セット分																		
天井 化粧石膏ボード撤	アスベスト含有建材	m2	0.60	x	0.60											0.36	0.36	m2	0.4
	t=9.5 区画養生、湿潤養生共																		
	床壁、区画養生(23.2m2)																		
消耗品	防塵マスク(レベル3対応)	式	1.00													1.00	1.00	式	1.0
	作業服、手袋																		
	1セット分																		
218. 屋外便所 1階																			
タイル工事																			
床 タイル	既存類似品 50角	m2	5.00	x	2.70											13.50			
			3.10	x	10.00											31.00	44.50	m2	44.5
左官工事																			
床 タイル下モルタル	既存類似品 50角	m2	5.00	x	2.70											13.50			
			3.10	x	10.00											31.00	44.50	m2	44.5
建具工事																			
TB-9		カ所	1.00													1.00	1.00	カ所	1.0
トイレース 扉外開きに再	W=600 H=1900	カ所	5.00													5.00	5.00	カ所	5.0
トイレース 再取付け	W7980、H=1900、t40	カ所	1.00													1.00	1.00	カ所	1.0
	隔板W1140…7カ所																		
トイレース 再取付け	W2300、H=1900、t40	カ所	1.00													1.00	1.00	カ所	1.0
	隔板W1100…1カ所																		
L型アングル上下固定	サッシW1800*H1200	カ所	1.00													1.00	1.00	カ所	1.0
塗装工事																			
壁 EP-G塗	B種	m2	2.55	+	2.70	+	2.55	+	2.70		10.50								
	女子便所		10.50	x	2.50											26.25			
		窓	-1.80	x	-2.00											-3.60			
		片開きドア	-0.90	x	-2.00											-1.80			
	女子便所		2.45	+	2.70	+	2.45	+	2.70	=	10.30								
		m2	10.30	x	2.50											25.75			
		窓	-1.50	x	-0.60											-0.90			
		片開きドア	-0.90	x	-2.00											-1.80			
		片開きドア	-0.90	x	-0.60											-0.54			



数量算出書(建築)

名 称	摘要	拾														小計	合計	単位	改め計
天井 EP-G塗	石膏ボード面 B種	m2	0.91	x	0.91			=	0.83							0.83	1.19	m2	1.2
			0.60	x	0.60			=	0.36							0.36			
壁 EP-G塗	B種	m2	3.00	+	5.05	+	1.75	+	1.50	+	1.25	+	3.55	=	16.10	38.64	35.04	m2	35.0
			16.10	x	2.40			=	38.64							38.64			
			窓	-1.20	x	-1.50			=	-1.80									
	片開きドア		-0.90	x	-2.00			=	-1.80										
<b>内装工事</b>																			
天井 シーリング石膏	t=9.5	m2	0.91	x	0.91			=	0.83							0.83	1.19	m2	1.2
			0.60	x	0.60			=	0.36							0.36			
天井 化粧石膏ボード	t=9.5	m2	0.91	x	0.91			=	0.83							0.83	1.55	m2	1.6
			0.60	x	0.60			=	0.36							0.36			
			0.60	x	0.60			=	0.36							0.36			
<b>ユニット及びその他工事</b>																			
和式便器塞ぎ	0.7*0.4	カ所	1.00					=	1.00							1.00	1.00	カ所	1.0
<b>撤去工事</b>																			
床 コンクリートカッター切	t=150	m	0.70	+	0.40	+	0.70	+	0.40	=	2.20					2.20	2.20	m	2.2
床 コンクリート撤去	t=150 700*400	カ所	1.00					=	1.00							1.00	1.00	カ所	1.0
床 タイル撤去	50角 下地モルタル共	m2	3.00	x	5.00			=	15.00							15.00	13.13	m2	13.1
			-1.25	*	-1.50			=	-1.88							-1.88			
天井 シーリング石膏ボード撤去	アスベスト含有建材 t=9.5 区画養生、湿潤養生共 床壁:区画養生(83.4m2)	m2	0.91	x	0.91			=	0.83							0.83	1.19	m2	1.2
			0.60	x	0.60			=	0.36							0.36			
			0.60	x	0.60			=	0.36							0.36			
消耗品	防塵マスク(レベル3対応) 作業服、手袋 1セット分	式	1.00					=	1.00							1.00	1.00	式	1.0
天井 化粧石膏ボード撤去	アスベスト含有建材 t=9.5 区画養生、湿潤養生共 床壁:区画養生(139m2)	m2	0.91	x	0.91			=	0.83							0.83	1.55	m2	1.6
			0.60	x	0.60			=	0.36							0.36			
			0.60	x	0.60			=	0.36							0.36			
消耗品	防塵マスク(レベル3対応) 作業服、手袋 3セット分	式	1.00					=	1.00							1.00	1.00	式	1.0

数量算出書(建築)

名 称	摘要	拾														小計	合計	単位	改め計
軽量鉄骨天井下地撤去	LGS 野縁まで	m2	0.91	x	0.91			=	0.83							0.83			
			0.91	x	0.91			=	0.83							0.83	1.66	m2	1.7
和風便器撤去		カ所	1.00					=	1.00							1.00	1.00	カ所	1.0
<b>219. 車両整備場 2階</b>																			
<b>タイル工事</b>																			
床 タイル	既存類似品 50角	m2	3.00	x	3.80			=	11.40							11.40			
			3.00	x	5.00			=	15.00							15.00			
			-1.25	x	-1.50			=	-1.88							-1.88	24.53	m2	24.5
<b>左官工事</b>																			
床 タイル下モルタル	既存類似品 50角	m2	3.00	x	3.80			=	11.40							11.40			
			3.00	x	5.00			=	15.00							15.00			
			-1.25	x	-1.50			=	-1.88							-1.88	24.53	m2	24.5
<b>建具工事</b>																			
トイレ-ス 扉外開きに再	W=600 H=1900	カ所	1.00					=	1.00							1.00	1.00	カ所	1.0
トイレ-ス 再取付け	W3430、H=1900、t40	カ所	1.00					=	1.00							1.00	1.00	カ所	1.0
	隔板W990…2カ所																		
TB-11		カ所	1.00					=	1.00							1.00	1.00	カ所	1.0
<b>塗装工事</b>																			
天井 EP-G塗	石膏ボード面 B種	m2	0.60	x	0.60			=	0.36							0.36			
			0.60	x	0.60			=	0.36							0.36			
			0.60	x	0.60			=	0.36							0.36			
			0.60	x	0.60			=	0.36							0.36	1.44	m2	1.4
壁 EP-G塗	B種	m2	3.00	+	5.05	+	1.75	+	1.50	+	1.25	+	3.55	=	16.10				
	窓		16.10	x	2.40			=	38.64							38.64			
	片開きドア		-1.20	x	-1.50			=	-1.80							-1.80			
			-0.90	x	-2.00			=	-1.80							-1.80			
			3.00	+	3.80	+	3.00	+	3.80	=	13.60								
	窓	m2	13.60	x	2.40			=	32.64							32.64			
			-1.20	x	-1.50			=	-1.80							-1.80			
	片開きドア		-0.90	x	-2.00			=	-1.80							-1.80	64.08	m2	64.1
<b>内装工事</b>																			
天井 シーリング石膏	t=9.5	m2	0.60	x	0.60			=	0.36							0.36			
			0.60	x	0.60			=	0.36							0.36			
			0.60	x	0.60			=	0.36							0.36			
			0.60	x	0.60			=	0.36							0.36	1.44	m2	1.4
天井 化粧石膏	t=9.5	m2	0.60	x	0.60			=	0.36							0.36			
			0.60	x	0.60			=	0.36							0.36	0.72	m2	0.7

数量算出書(建築)

名 称	摘要	拾										小計	合計	単位	改め計			
<b>ユニット及びその他工事</b>																		
和式便器塞ぎ	0.7*0.4	カ所	2.00						=	2.00					2.00	2.00	カ所	2.0
<b>撤去工事</b>																		
床 コンクリートカッター切	t=150	m	0.70	+	0.40	+	0.70	+	0.40	=	2.20							
			2.20	x	2.00				=	4.40					4.40	4.40	m	4.4
床 コンクリート撤去	t=150 700*400	カ所	2.00						=	2.00					2.00	2.00	カ所	2.0
床 タイル撤去	50角 下地モルタル共	m2	3.00	x	3.80				=	11.40					11.40			
			3.00	x	5.00				=	15.00					15.00			
			-1.25	x	-1.50				=	-1.88					-1.88	24.53	m2	24.5
天井 シーリング石膏ボード撤去	アスベスト含有建材	m2	0.60	x	0.60				=	0.36					0.36			
	t=9.5 区画養生、湿潤養生共		0.60	x	0.60				=	0.36					0.36			
	床壁:区画養生(167m2)		0.60	x	0.60				=	0.36					0.36			
			0.60	x	0.60				=	0.36					0.36	1.44	m2	1.4
消耗品	防塵マスク(レベル3対応)	式	1.00						=	1.00					1.00	1.00	式	1.0
	作業服、手袋																	
	2セット分																	
天井 化粧石膏ボード撤去	アスベスト含有建材	m2	0.60	x	0.60				=	0.36					0.36			
	t=9.5 区画養生、湿潤養生共		0.60	x	0.60				=	0.36					0.36	0.72	m2	0.7
	床壁:区画養生(46.4m2)																	
消耗品	防塵マスク(レベル3対応)	式	1.00						=	1.00					1.00	1.00	式	1.0
	作業服、手袋																	
	2セット分																	
和風便器撤去		カ所	2.00						=	2.00					2.00	2.00	カ所	2.0
トイレブース撤去	W3665、H1900、t40	カ所	1.00						=	1.00					1.00	1.00	カ所	1.0
	隔板W1000...2カ所																	
<b>222.隊舎(1F)</b>																		
<b>金属工事</b>																		
軽量鉄骨天井下地	19型 直張	m2	0.91	x	0.91				=	0.83					0.83	0.83	m2	0.8
<b>塗装工事</b>																		
天井 EP-G塗	石膏ボード面 B種	m2	0.91	x	0.91				=	0.83					0.83	0.83	m2	0.8
<b>内装工事</b>																		

数量算出書(建築)

名 称	摘要	拾														小計	合計	単位	改め計
天井 シーリング石膏ボード	t=9.5	m2	0.91	x	0.91			=	0.83							0.83	0.83	m2	0.8
<b>撤去工事</b>																			
天井 シーリング石膏ボード撤去	アスベスト含有建材 t=9.5 区画養生、湿潤養生共 床壁・区画養生(72.7m2)	m2	0.91	x	0.91			=	0.83							0.83	0.83	m2	0.8
<b>消耗品</b>																			
	防塵マスク(レベル3対応) 作業服、手袋 1セット分	式	1.00					=	1.00							1.00	1.00	式	1.0
軽量鉄骨天井下地撤去	LGS 野縁まで	m2	0.91	x	0.91			=	0.83							0.83	0.83	m2	0.8
<b>222. 隊舎 2階</b>																			
<b>タイル工事</b>																			
床 タイル	既存類似品 50角	m2	3.27	x	7.05			=	23.05							23.05	23.05	m2	23.1
<b>金属工事</b>																			
軽量鉄骨天井下	19型 直張	m2	0.91	x	0.91			=	0.83							0.83	0.83	m2	0.8
<b>左官工事</b>																			
床 タイル下モルタル	既存類似品 50角	m2	3.27	x	7.05			=	23.05							23.05	23.05	m2	23.1
<b>建具工事</b>																			
トイレブース 扉外開きに再	W=600 H=1900	カ所	1.00					=	1.00							1.00	1.00	カ所	1.0
トイレブース 再取付け	W4710、H=1900、t40 隔板W1090…5カ所	カ所	1.00					=	1.00							1.00	1.00	カ所	1.0
<b>塗装工事</b>																			
天井 EP-G塗	石膏ボード面 B種	m2	0.91	x	0.91			=	0.83							0.83	0.83	m2	0.8
壁 EP-G塗	B種	m2	3.27	+	7.05	+	3.27	+	7.05	+	0.70	+	0.70	+		52.22			
	片開きドア		-0.90	x	-2.00	x	2.00	=	-3.60							-3.60	48.62	m2	48.6
<b>内装工事</b>																			
天井 シーリング石膏ボード	t=9.5	m2	0.91	x	0.91			=	0.83							0.83	0.83	m2	0.8
天井 化粧石膏ボード	t=9.5	m2	0.60	x	0.60			=	0.36							0.36			

数量算出書(建築)

名 称	摘要	拾										小計	合計	単位	改め計		
			0.60	x	0.60			=	0.36				0.36	0.72	m2	0.7	
<b>ユニット及びその他工事</b>																	
和式便器塞ぎ	0.7*0.4	カ所	1.00					=	1.00				1.00	1.00	カ所	1.0	
<b>撤去工事</b>																	
床 コンクリートカッター切	t=150	m	0.70	+	0.40	+	0.70	+	0.40	=	2.20		2.20	2.20	m	2.2	
床 コンクリート撤去	t=150 700*400	カ所	1.00					=	1.00				1.00	1.00	カ所	1.0	
床 タイル撤去	50角 下地モルタル共	m2	3.28	x	7.05			=	23.12				23.12	23.12	m2	23.1	
天井 シーズン石膏ボード撤去	アスベスト含有建材 t=9.5 区画養生、湿潤養生共 床壁・区画養生(72.7m2)	m2	0.91	x	0.91			=	0.83				0.83	0.83	m2	0.8	
消耗品	防塵マスク(レベル3対応) 作業服、手袋 1セット分	式	1.00					=	1.00				1.00	1.00	式	1.0	
天井 化粧石膏ボード撤去	アスベスト含有建材 t=9.5 区画養生、湿潤養生共 床壁・区画養生(49.1m2)	m2	0.60	x	0.60			=	0.36				0.36	0.72	m2	0.7	
消耗品	防塵マスク(レベル3対応) 作業服、手袋 2セット分	式	1.00					=	1.00				1.00	1.00	式	1.0	
軽量鉄骨天井下地撤去	LGS 野縁まで	m2	0.91	x	0.91			=	0.83				0.83	0.83	m2	0.8	
和風便器撤去		カ所	1.00					=	1.00				1.00	1.00	カ所	1.0	
<b>222. 隊舎 3階</b>																	
<b>タイル工事</b>																	
床 タイル	既存類似品 50角	m2	3.28	x	7.05			=	23.12				23.12	23.12	m2	23.1	
<b>金属工事</b>																	
軽量鉄骨天井下	19型 直張	m2	0.91	x	0.91			=	0.83				0.83	0.83	m2	0.8	
<b>左官工事</b>																	
床 タイル下モルタル	既存類似品 50角	m2	3.28	x	7.05			=	23.12				23.12	23.12	m2	23.1	
<b>建具工事</b>																	
トイレブース 扉外開きに再	W=600 H=1900	カ所	1.00					=	1.00				1.00	1.00	カ所	1.0	
トイレブース 再取付け	W4710、H=1900、t40	カ所	1.00					=	1.00				1.00	1.00	カ所	1.0	

数量算出書(建築)

名 称	摘要	拾													小計	合計	単位	改め計			
	隔板W1130…5カ所																				
<b>塗装工事</b>																					
天井 EP-G塗	石膏ボード面 B種	m2	0.60	x	0.60	=	0.36										0.36				
			0.60	x	0.60	=	0.36										0.36	0.72	m2	0.7	
壁 EP-G塗	B種		3.27	+	7.05	+	3.27	+	7.05	+	0.70	+	0.70	+							
		m2	0.70	+	0.70	=	21.76	x	2.40	=	52.22							52.22			
	片開きドア		-0.90	x	-2.00	x	2.00	=	-3.60									-3.60	48.62	m2	48.6
<b>内装工事</b>																					
天井 シーリング石膏	t=9.5	m2	0.60	x	0.60	=	0.36											0.36			
			0.60	x	0.60	=	0.36											0.36	0.72	m2	0.7
天井 化粧石膏ボード	t=9.5	m2	0.60	x	0.60	=	0.36											0.36			
			0.60	x	0.60	=	0.36											0.36	0.72	m2	0.7
<b>ユニット及びその他工事</b>																					
和式便器塞ぎ	0.7*0.4	カ所	1.00			=	1.00											1.00	1.00	カ所	1.0
<b>撤去工事</b>																					
床 コンクリートカッター切	t=150	m	0.70	+	0.40	+	0.70	+	0.40	=	2.20							2.20	2.20	m	2.2
床 コンクリート撤去	t=150 700*400	カ所	1.00			=	1.00											1.00	1.00	カ所	1.0
床 タイル撤去	50角 下地モルタル共	m2	3.28	x	7.05	=	23.12											23.12	23.12	m2	23.1
天井 シーリング石膏ボード撤去	アスベスト含有建材 t=9.5 区画養生、湿潤養生共	m2	0.91	x	0.91	=	0.83											0.83	0.83	m2	0.8
	床壁:区画養生(72.7m2)																				
消耗品	防塵マスク(レベル3対応) 作業服、手袋 1セット分	式	1.00			=	1.00											1.00	1.00	式	1.0
天井 化粧石膏ボード撤去	アスベスト含有建材 t=9.5 区画養生、湿潤養生共	m2	0.60	x	0.60	=	0.36											0.36			
	床壁:区画養生(49.1m2)		0.60	x	0.60	=	0.36											0.36	0.72	m2	0.7
消耗品	防塵マスク(レベル3対応) 作業服、手袋 2セット分	式	1.00			=	1.00											1.00	1.00	式	1.0
軽量鉄骨天井下地撤去	LGS 野縁まで	m2	0.91	x	0.91	=	0.83											0.83	0.83	m2	0.8

数量算出書(建築)

名 称	摘要	拾														小計	合計	単位	改め計	
		カ所	1.00																	
和風便器撤去		カ所	1.00					=	1.00								1.00	1.00	カ所	1.0
222. 隊舎 4階																				
タイル工事																				
床 タイル	既存類似品 50角	m2	3.28	x	7.05			=	23.12								23.12	23.12	m2	23.1
左官工事																				
床 タイル下モルタル	既存類似品 50角	m2	3.28	x	7.05			=	23.12								23.12	23.12	m2	23.1
建具工事																				
TB-10		カ所	1.00					=	1.00								1.00	1.00	カ所	1.0
塗装工事																				
天井 EP-G塗	石膏ボード面 B種	m2	0.60	x	0.60			=	0.36								0.36	0.36	m2	0.4
壁 EP-G塗	B種		3.27	+	7.05	+	3.27	+	7.05	+	0.70	+	0.70	+						
		m2	0.70	+	0.70	=	21.76	x	2.40	=	52.22						52.22			
	片開きドア		-0.90	x	-2.00	x	2.00	=	-3.60								-3.60	48.62	m2	48.6
内装工事																				
天井 シーリング石膏	t=9.5	m2	0.60	x	0.60			=	0.36								0.36	0.36	m2	0.4
天井 化粧石膏	t=9.5	m2	0.60	x	0.60			=	0.36								0.36			
			0.60	x	0.60			=	0.36								0.36	0.72	m2	0.7
ユニット及びその他工事																				
和式便器塞ぎ	0.7*0.4	カ所	1.00					=	1.00								1.00	1.00	カ所	1.0
撤去工事																				
床 コンクリートカッター切	t=150	m	0.70	+	0.40	+	0.70	+	0.40	=	2.20						2.20	2.20	m	2.2
床 コンクリート撤去	t=150 700*400	カ所	1.00					=	1.00								1.00	1.00	カ所	1.0
床 タイル撤去	50角 下地モルタル共	m2	3.28	x	7.05			=	23.12								23.12	23.12	m2	23.1
天井 シーリング石膏ボード撤去	アスベスト含有建材	m2	0.60	x	0.60			=	0.36								0.36	0.36	m2	0.4
	t=9.5 区画養生、湿润養生共																			
	床壁、区画養生(72.7m2)																			
消耗品	防塵マスク(レベル3対応)	式	1.00					=	1.00								1.00	1.00	式	1.0
	作業服、手袋																			
	1セット分																			
天井 化粧石膏ボード撤去	アスベスト含有建材	m2	0.60	x	0.60			=	0.36								0.36			
	t=9.5 区画養生、湿润養生共		0.60	x	0.60			=	0.36								0.36	0.72	m2	0.7
	床壁、区画養生(49.1m2)																			

数量算出書(建築)

名 称	摘要	拾													小計	合計	単位	改め計		
消耗品	防塵マスク(レベル3対応)	式	1.00														1.00	1.00	式	1.0
	作業服、手袋																			
	2セット分																			
和風便器撤去		カ所	1.00														1.00	1.00	カ所	1.0
トイレブース撤去	W4710、H1900、t40	カ所	1.00														1.00	1.00	カ所	1.0
	隔板W1200…5カ所																			
222. 隊舎 5階																				
金属工事																				
軽量鉄骨天井下	19型 直張	m2	0.91	x	4.55												4.14	4.14	m2	4.2
塗装工事																				
天井 EP-G塗	石膏ボード面 B種	m2	0.91	x	4.55												4.14	4.14	m2	4.2
壁 EP-G塗	B種		3.27	+	7.05	+	3.27	+	7.05	+	0.70	+	0.70	+						
		m2	0.70	+	0.70	=	21.76	x	2.40	=	52.22						52.22			
	片開きドア		-0.90	x	-2.00	x	2.00	=	-3.60								-3.60	48.62	m2	48.6
内装工事																				
天井 シーリング石	t=9.5	m2	0.91	x	4.55												4.14	4.14	m2	4.2
天井 化粧石膏ホ	t=9.5	m2	0.60	x	0.60												0.36			
			0.60	x	0.60												0.36	0.72	m2	0.7
撤去工事																				
天井 シーリング石膏ボード撤去	アスベスト含有建材	m2	0.91	x	4.55												4.14	4.14	m2	4.2
	t=9.5 区画養生、湿潤養生共																			
	床壁:区画養生(72.7m2)																			
消耗品	防塵マスク(レベル3対応)	式	1.00														1.00	1.00	式	1.0
	作業服、手袋																			
	1セット分																			
天井 化粧石膏ボード撤	アスベスト含有建材	m2	0.60	x	0.60												0.36			
	t=9.5 区画養生、湿潤養生共		0.60	x	0.60												0.36	0.72	m2	0.7
	床壁:区画養生(49.1m2)																			
消耗品	防塵マスク(レベル3対応)	式	1.00														1.00	1.00	式	1.0
	作業服、手袋																			
	2セット分																			

数量算出書(建築)

名 称	摘要	拾										小計	合計	単位	改め計		
軽量鉄骨天井下地撤去	LGS 野縁まで	m2	0.91	x	4.55			=	4.14					4.14	4.14	m2	4.2
<b>222. 隊舎 6階</b>																	
<b>タイル工事</b>																	
床 タイル	既存類似品 50角	m2	5.80	x	7.05			=	40.89					40.89			
			-1.10	x	-1.85			=	-2.04					-2.04			
			-0.45	x	-0.85			=	-0.38					-0.38			
	間仕切り壁		-1.30	x	-0.15	x	-2.00	=	-0.39					-0.39			
	間仕切り壁		-0.30	x	-3.60			=	1.08					1.08	39.16	m2	39.2
<b>金属工事</b>																	
軽量鉄骨天井下	19型 直張	m2	0.91	x	4.55			=	4.14					4.14	4.14	m2	4.2
<b>左官工事</b>																	
床 タイル下モルタル		m2	5.80	x	7.05			=	40.89					40.89			
			-1.10	x	-1.85			=	-2.04					-2.04			
			-0.45	x	-0.85			=	-0.38					-0.38			
	間仕切り壁		-1.30	x	-0.15	x	-2.00	=	-0.39					-0.39			
	間仕切り壁		-0.30	x	-3.60			=	1.08					1.08	39.16	m2	39.2
<b>建具工事</b>																	
トイレース 再取付け	W5060、H=1900、t40 隔板W1270…5カ所	カ所	1.00					=	1.00					1.00	1.00	カ所	1.0
トイレース 再取付け	W6450、H=1900、t40 隔板W1080…5カ所	カ所	1.00					=	1.00					1.00	1.00	カ所	1.0
<b>塗装工事</b>																	
天井 EP-G塗	石膏ボード面 B種	m2	0.91	x	4.55			=	4.14					4.14	4.14	m2	4.2
壁 EP-G塗	B種		5.80	+	7.05	+	5.80	+	7.05	=	25.70						
		m2	25.70	x	2.40	=	61.68							61.68			
			1.30	+	0.15	+	0.15	+	1.00	=	2.60						
		m2	2.60	x	2.40	x	2.00	=	12.48					12.48			
	片開きドア		-0.90	x	-2.00	x	2.00	=	-3.60					-3.60			
	片開きドア		-0.90	x	-2.00	x	2.00	=	-3.60					-3.60	66.96	m2	67.0
<b>内装工事</b>																	
天井 シーリング石t=9.5		m2	0.91	x	4.55			=	4.14					4.14	4.14	m2	4.2
天井 化粧石膏ホt=9.5		m2	0.60	x	0.60			=	0.36					0.36			
			0.60	x	0.60			=	0.36					0.36	0.72	m2	0.7
<b>ユニット及びその他工事</b>																	

数量算出書(建築)

名称	摘要	拾										小計	合計	単位	改め計		
和式便器塞ぎ	0.7*0.4	カ所	4.00					=	4.00					4.00	4.00	カ所	4.0
<b>撤去工事</b>																	
床 コンクリートカッター切	t=150	m	0.70	+	0.40	+	0.70	+	0.40	=	2.20						
			2.20	x	4.00			=	8.80					8.80	8.80	m	8.8
床 コンクリート撤去	t=150 700*400	カ所	4.00					=	4.00					4.00	4.00	カ所	4.0
床 タイル撤去	50角 下地モルタル共	m2	5.80	x	7.05			=	40.89					40.89			
			1.10	x	1.85			=	-2.04					-2.04			
			0.15	x	1.30			=	-0.20					-0.20			
			0.15	x	1.30			=	-0.20					-0.20			
			0.30	x	3.60			=	-1.08					-1.08			
			0.45	x	0.85			=	-0.38					-0.38	37.00	m2	37.0
天井 シーリング石膏ボード撤去	アスベスト含有建材 t=9.5 区画養生、湿潤養生共 床壁:区画養生(103m2)	m2	0.91	x	4.55			=	4.14					4.14	4.14	m2	4.2
消耗品	防塵マスク(レベル3対応) 作業服、手袋 1セット分	式	1.00					=	1.00					1.00	1.00	式	1.0
天井 化粧石膏ボード撤去	アスベスト含有建材 t=9.5 区画養生、湿潤養生共 床壁:区画養生(49.1m2)	m2	0.60	x	0.60			=	0.36					0.36	0.72	m2	0.7
消耗品	防塵マスク(レベル3対応) 作業服、手袋 2セット分	式	1.00					=	1.00					1.00	1.00	式	1.0
軽量鉄骨天井下地撤去	LGS 野縁まで	m2	0.91	x	4.55			=	4.14					4.14	4.14	m2	4.2
和風便器撤去		カ所	4.00					=	4.00					4.00	4.00	カ所	4.0
<b>222. 隊舎 7階</b>																	
<b>タイル工事</b>																	
床 タイル	既存類似品 50角	m2	5.80	x	7.05			=	40.89					40.89			
			-1.10	x	-1.85			=	-2.04					-2.04			
			-0.45	x	-0.85			=	-0.38					-0.38			
		間仕切り壁	-1.30	x	-0.15	x	-2.00	=	-0.39					-0.39			
		間仕切り壁	-0.30	x	-3.60			=	1.08					1.08	39.16	m2	39.2
<b>金属工事</b>																	

数量算出書(建築)

名 称	摘要	拾										小計	合計	単位	改め計		
軽量鉄骨天井	19型 直張	m2	0.91	x	4.55			=	4.14					4.14	4.14	m2	4.2
<b>左官工事</b>																	
床 タイル下モルタル		m2	5.80	x	7.05			=	40.89					40.89			
			-1.10	x	-1.85			=	-2.04					-2.04			
			-0.45	x	-0.85			=	-0.38					-0.38			
	間仕切り壁		-1.30	x	-0.15	x	-2.00	=	-0.39					-0.39			
	間仕切り壁		-0.30	x	-3.60			=	1.08					1.08	39.16	m2	39.2
<b>建具工事</b>																	
トイレス 再取付け	W5060、H=1900、t40	カ所	1.00					=	1.00					1.00	1.00	カ所	1.0
	隔板W1270…5カ所																
トイレス 再取付け	W6450、H=1900、t40	カ所	1.00					=	1.00					1.00	1.00	カ所	1.0
	隔板W1080…5カ所																
<b>塗装工事</b>																	
天井 EP-G塗	石膏ボード面 B種	m2	0.91	x	4.55			=	4.14					4.14	4.14	m2	4.2
壁 EP-G塗	B種		5.80	+	7.05	+	5.80	+	7.05	=	25.70						
		m2	25.70	x	2.40	=	61.68							61.68			
			1.30	+	0.15	+	0.15	+	1.00	=	2.60						
		m2	2.60	x	2.40	x	2.00	=	12.48					12.48			
	片開きドア		-0.90	x	-2.00	x	2.00	=	-3.60					-3.60			
	片開きドア		-0.90	x	-2.00	x	2.00	=	-3.60					-3.60	66.96	m2	67.0
<b>内装工事</b>																	
天井 シーリング石	t=9.5	m2	0.91	x	4.55			=	4.14					4.14	4.14	m2	4.2
天井 化粧石膏ホ	t=9.5	m2	0.60	x	0.60			=	0.36					0.36			
			0.60	x	0.60			=	0.36					0.36	0.72	m2	0.7
<b>ユニット及びその他工事</b>																	
和式便器塞ぎ	0.7*0.4	カ所	4.00					=	4.00					4.00	4.00	カ所	4.0
<b>撤去工事</b>																	
床 コンクリートカッター切	t=150	m	0.70	+	0.40	+	0.70	+	0.40	=	2.20						
			2.20	x	4.00			=	8.80					8.80	8.80	m	8.8
床 コンクリート撤去	t=150 700*400	カ所	4.00					=	4.00					4.00	4.00	カ所	4.0
床 タイル撤去	50角 下地モルタル共	m2	5.80	x	7.05			=	40.89					40.89			
			1.10	x	1.85			=	-2.04					-2.04			
			0.15	x	1.30			=	-0.20					-0.20			
			0.15	x	1.30			=	-0.20					-0.20			

数量算出書(建築)

名 称	摘要	拾										小計	合計	単位	改め計			
			0.30	x	3.60			=	-1.08									
			0.45	x	0.85			=	-0.38									
天井 シーズン石膏ボード撤去	アスベスト含有建材	m2	0.91	x	4.55			=	4.14									
	t=9.5 区画養生、湿潤養生共																	
	床壁:区画養生(103m2)																	
消耗品	防護マスク(レベル3対応)	式	1.00					=	1.00									
	作業服、手袋																	
	1セット分																	
天井 化粧石膏ボード撤去	アスベスト含有建材	m2	0.60	x	0.60			=	0.36									
	t=9.5 区画養生、湿潤養生共		0.60	x	0.60			=	0.36									
	床壁:区画養生(49.1m2)																	
消耗品	防護マスク(レベル3対応)	式	1.00					=	1.00									
	作業服、手袋																	
	2セット分																	
軽量鉄骨天井下地撤去	LGS 野縁まで	m2	0.91	x	4.55			=	4.14									
和風便器撤去		カ所	4.00					=	4.00									
222. 隊舎 8階																		
タイル工事																		
床 タイル	既存類似品 50角	m2	5.80	x	7.05			=	40.89									
			-1.10	x	-1.85			=	-2.04									
			-0.45	x	-0.85			=	-0.38									
	間仕切り壁		-1.30	x	-0.15	x	-2.00	=	-0.39									
	間仕切り壁		-0.30	x	-3.60			=	1.08									
左官工事																		
床 タイル下モルタル	既存類似品 50角	m2	5.80	x	7.05			=	40.89									
			-1.10	x	-1.85			=	-2.04									
			-0.45	x	-0.85			=	-0.38									
	間仕切り壁		-1.30	x	-0.15	x	-2.00	=	-0.39									
	間仕切り壁		-0.30	x	-3.60			=	1.08									
建具工事																		
トイレース 再取付け	W5060、H=1900、t40	カ所	1.00					=	1.00									
	隔板W1270…5カ所																	
トイレース 再取付け	W6450、H=1900、t40	カ所	1.00					=	1.00									
	隔板W1080…5カ所																	
塗装工事																		



数量算出書(建築)

名 称	摘要	拾														小計	合計	単位	改め計
消耗品	防塵マスク(レベル3対応)	式	1.00					=	1.00							1.00	1.00	式	1.0
	作業服、手袋																		
	2セット分																		
和風便器撤去		カ所	4.00					=	4.00							4.00	4.00	カ所	4.0
224.整備場(1F)																			
タイル工事																			
床 タイル	既存類似品 50角	m2	4.35	x	1.95			=	8.48							8.48			
			3.10	x	1.55			=	4.81							4.81	13.29	m2	13.3
金属工事																			
軽量鉄骨天井	19型 直張	m2	0.91	x	0.91			=	0.83							0.83	0.83	m2	0.8
左官工事																			
床 タイル下モルタル	既存類似品 50角	m2	4.35	x	1.95			=	8.48							8.48			
			3.10	x	1.55			=	4.81							4.81	13.29	m2	13.3
建具工事																			
トイレース 再取付け	W2950、H=1900、t40	カ所	1.00					=	1.00							1.00	1.00	カ所	1.0
	隔板W1070…1カ所																		
塗装工事																			
天井 EP-G塗	石膏ボード面 B種	m2	0.60	x	0.60			=	0.36							0.36			
			0.91	x	0.91			=	0.83							0.83	1.19	m2	1.2
壁 EP-G塗	B種		4.35	+	1.95	+	1.25	+	1.55	+	3.10	+	3.50	=	15.70				
		m2	15.70	x	2.50	=	39.25									39.25			
	片開きドア		-0.90	x	-2.00			=	-1.80							-1.80			
	片開きドア		-0.60	x	-1.50			=	-0.90							-0.90			
	窓		-1.20	x	-1.50			=	-1.80							-1.80	34.75	m2	34.8
内装工事																			
天井 シーリング石	t=9.5	m2	0.60	x	0.60			=	0.36							0.36			
			0.91	x	0.91			=	0.83							0.83	1.19	m2	1.2
天井 化粧石膏ホ	t=9.5	m2	0.60	x	0.60			=	0.36							0.36	0.36	m2	0.4
ユニット及びその他工事																			
和式便器塞ぎ	0.7*0.4	カ所	1.00					=	1.00							1.00	1.00	カ所	1.0
撤去工事																			
床 コンクリートカッター切	t=150	m	0.70	+	0.40	+	0.70	+	0.40	=	2.20					2.20	2.20	m	2.2
床 コンクリート撤去	t=150 700*400	カ所	1.00					=	1.00							1.00	1.00	カ所	1.0

数量算出書(建築)

名称	摘要	拾	い	小計	合計	単位	改め計
床 タイル撤去	50角 下地モルタル共	m2	4.35 x 3.50 = 15.23 1.25 x 1.55 = -1.94 0.45 x 0.85 = -0.38	15.23 -1.94 -0.38	12.91	m2	12.9
天井 シーズン石膏ボード撤去	アスベスト含有建材	m2	0.60 x 0.60 = 0.36 t=9.5 区画養生、湿潤養生共 0.91 x 0.91 = 0.83 床壁:区画養生(71m2)	0.36 0.83	1.19	m2	1.2
消耗品	防塵マスク(レベル3対応) 作業服、手袋 1セット分	式	1.00 = 1.00	1.00	1.00	式	1.0
天井 化粧石膏ボード撤去	アスベスト含有建材	m2	0.60 x 0.60 = 0.36 t=9.5 区画養生、湿潤養生共 床壁:区画養生(23.2m2)	0.36	0.36	m2	0.4
消耗品	防塵マスク(レベル3対応) 作業服、手袋 1セット分	式	1.00 = 1.00	1.00	1.00	式	1.0
和風便器撤去		カ所	1.00 = 1.00	1.00	1.00	カ所	1.0
軽量鉄骨天井下地撤去	LGS 野縁まで	m2	0.91 x 0.91 = 0.83	0.83	0.83	m2	0.8
224.整備場(2F)							
タイル工事							
床 タイル	既存類似品 50角	m2	5.20 x 2.20 = 11.44 1.20 x 0.35 = 0.42 3.10 x 1.55 = 4.81	11.44 0.42 4.81	16.67	m2	16.7
左官工事							
床 タイル下モルタル		m2	5.20 x 2.20 = 11.44 1.20 x 0.35 = 0.42 3.10 x 1.55 = 4.81	11.44 0.42 4.81	16.67	m2	16.7
建具工事							
トイレブース 再取付け	W2950、H=1900、t40 隔板W1380…2カ所	カ所	1.00 = 1.00	1.00	1.00	カ所	1.0
塗装工事							
天井 EP-G塗	石膏ボード面 B種	m2	0.60 x 0.60 = 0.36 0.60 x 0.60 = 0.36	0.36 0.36	0.72	m2	0.7
壁 EP-G塗	B種		5.20 + 2.55 + 1.20 + 0.35 + 0.90 + 1.55 + 3.10 +				



数量算出書(建築)

名 称	摘要	拾														小計	合計	単位	改め計	
仮設																				
1.広告資料館																				
脚立足場	運搬費込	m2	3.64	x	1.37	=	4.99										4.99	4.99	m2	5.0
	H=1.8m 並列(1ヶ月)																			
床養生	ブルーシート	m2	3.64	x	1.37	=	4.99										4.99	4.99	m2	5.0
竣工時清掃後片付け		m2	3.64	x	1.37	=	4.99										4.99	4.99	m2	5.0
70.便所																				
脚立足場	運搬費込	m2	0.60	x	0.60	=	0.36										0.36			
	H=1.8m 並列(1ヶ月)		0.60	x	0.60	=	0.36										0.36	0.72	m2	0.7
床養生	ブルーシート	m2	3.86	x	2.95	=	11.39										11.39	11.39	m2	11.4
竣工時清掃後片付け		m2	3.86	x	2.95	=	11.39										11.39	11.39	m2	11.4
123隊舎 1階																				
脚立足場	運搬費込	m2	0.91	x	1.82	=	1.66										1.66			
	H=1.8m 並列(1ヶ月)		0.91	x	1.82	=	1.66										1.66	3.31	m2	3.3
床養生	ブルーシート	m2	5.80	x	6.94	=	40.25										40.25			
			-2.90	x	-2.30	=	-6.67										-6.67	33.58	m2	33.6
竣工時清掃後片付け		m2	5.80	x	6.94	=	40.25										40.25			
			-2.90	x	-2.30	=	-6.67										-6.67	33.58	m2	33.6
123隊舎 2階																				
脚立足場	運搬費込	m2	5.80	x	6.97	=	40.43										40.43			
	H=1.8m 並列(1ヶ月)		0.60	x	0.60	=	0.36										0.36			
			0.60	x	0.60	=	0.36										0.36	41.15	m2	41.2
床養生	ブルーシート	m2	5.80	x	6.97	=	40.43										40.43	40.43	m2	40.4
竣工時清掃後片付け		m2	5.80	x	6.97	=	40.43										40.43	40.43	m2	40.4
123隊舎 3階																				
脚立足場	運搬費込	m2	5.80	x	6.97	=	40.43										40.43			
	H=1.8m 並列(1ヶ月)		0.60	x	0.60	=	0.36										0.36			
			0.60	x	0.60	=	0.36										0.36	41.15	m2	41.2
床養生	ブルーシート	m2	5.80	x	6.97	=	40.43										40.43	40.43	m2	40.4

数量算出書(建築)

名 称	摘要	拾										小計	合計	単位	改め計			
竣工時清掃後片付け		m2	5.80	x	6.97			=	40.43						40.43	40.43	m2	40.4
172隊舎 1階																		
脚立足場	運搬費込	m2	1.80	x	1.30			=	2.34						2.34			
	H=1.8m 並列(1ヶ月)		0.60	x	0.60			=	0.36						0.36	2.70	m2	2.7
床養生	ブルーシート	m2	1.80	x	1.30			=	2.34						2.34	2.34	m2	2.3
竣工時清掃後片付け		m2	1.80	x	1.30			=	2.34						2.34	2.34	m2	2.3
175本部隊舎 1階																		
脚立足場	運搬費込	m2	0.91	x	0.91			=	0.83						0.83	0.83	m2	0.8
	H=1.8m 並列(1ヶ月)																	
床養生	ブルーシート	m2	3.12	x	7.05			=	22.00						22.00	22.00	m2	22.0
竣工時清掃後片付け		m2	3.12	x	7.05			=	22.00						22.00	22.00	m2	22.0
175本部隊舎 2階																		
脚立足場	運搬費込	m2	3.12	x	7.05			=	22.00						22.00	22.00	m2	22.0
	H=1.8m 並列(1ヶ月)																	
床養生	ブルーシート	m2	3.12	x	7.05			=	22.00						22.00	22.00	m2	22.0
竣工時清掃後片付け		m2	3.12	x	7.05			=	22.00						22.00	22.00	m2	22.0
175本部隊舎 3階																		
脚立足場	運搬費込	m2	3.12	x	2.65			=	8.27						8.27	8.27	m2	8.3
	H=1.8m 並列(1ヶ月)																	
床養生	ブルーシート	m2	3.12	x	2.65			=	8.27						8.27	8.27	m2	8.3
竣工時清掃後片付け		m2	3.12	x	2.65			=	8.27						8.27	8.27	m2	8.3
195需品整備工場 1階																		
脚立足場	運搬費込	m2	3.60	x	2.00			=	7.20						7.20			
	H=1.8m 並列(1ヶ月)		0.60	x	0.60			=	0.36						0.36			
			0.60	x	0.60			=	0.36						0.36	7.92	m2	7.9
床養生	ブルーシート	m2	3.60	x	2.00			=	7.20						7.20	7.20	m2	7.2
竣工時清掃後片付け		m2	3.60	x	2.00			=	7.20						7.20	7.20	m2	7.2
201隊舎 4階																		

数量算出書(建築)

名 称	摘要	拾										小計	合計	単位	改め計	
脚立足場	運搬費込	m2	0.60	x	0.60	=	0.36						0.36	0.36	m2	0.4
	H=1.8m 並列(1ヶ月)															
竣工時清掃後片付け		m2	3.12	x	3.43	=	10.70						10.70	10.70	m2	10.7
<b>204 体育館</b>																
脚立足場	運搬費込	m2	3.30	x	4.20	=	13.86						13.86			
	H=1.8m 並列(1ヶ月)		3.30	x	3.40	=	11.22						11.22			
			0.60	x	0.60	=	0.36						0.36			
			0.60	x	0.60	=	0.36						0.36	25.80	m2	25.8
床養生	ブルーシート	m2	3.30	x	4.20	=	13.86						13.86			
			3.30	x	3.40	=	11.22						11.22	25.08	m2	25.1
竣工時清掃後片付け		m2	3.30	x	4.20	=	13.86						13.86			
			3.30	x	3.40	=	11.22						11.22	25.08	m2	25.1
<b>208 整備工場 1階</b>																
脚立足場	運搬費込	m2	5.20	x	4.50	=	23.40						23.40	23.40	m2	23.4
	H=1.8m 並列(1ヶ月)															
床養生	ブルーシート	m2	5.20	x	4.50	=	23.40						23.40	23.40	m2	23.4
竣工時清掃後片付け		m2	5.20	x	4.50	=	23.40						23.40	23.40	m2	23.4
<b>211. 医務室 1階</b>																
脚立足場	運搬費込	m2	5.00	x	2.10	=	10.50						10.50			
	H=1.8m 並列(1ヶ月)		2.90	x	0.90	=	2.61						2.61			
			0.60	x	0.60	=	0.36						0.36			
			0.60	x	0.60	=	0.36						0.36			
			0.60	x	0.60	=	0.36						0.36	14.19	m2	14.2
床養生	ブルーシート	m2	5.00	x	2.10	=	10.50						10.50			
			2.90	x	0.90	=	2.61						2.61	13.11	m2	13.1
竣工時清掃後片付け		m2	5.00	x	2.10	=	10.50						10.50			
			2.90	x	0.90	=	2.61						2.61	13.11	m2	13.1
<b>212. 給油取扱所 1階</b>																
脚立足場	運搬費込	m2	2.40	x	2.70	=	6.48						6.48			
	H=1.8m 並列(1ヶ月)		0.60	x	0.60	=	0.36						0.36	6.84	m2	6.8
床養生	ブルーシート	m2	2.40	x	2.70	=	6.48						6.48	6.48	m2	6.5
竣工時清掃後片付け		m2	2.40	x	2.70	=	6.48						6.48	6.48	m2	6.5

数量算出書(建築)

名 称	摘要	拾														小計	合計	単位	改め計
<b>216. 給排水所 1階</b>																			
脚立足場	運搬費込	m2	1.30	x	2.00	=	2.60											2.60	
	H=1.8m 並列(1ヶ月)		0.60	x	0.60	=	0.36											0.36	
																		2.96	
床養生	ブルーシート	m2	1.30	x	2.00	=	2.60											2.60	
																		2.60	
竣工時清掃後片付け		m2	1.30	x	2.00	=	2.60											2.60	
																		2.60	
<b>217. 隊舎 5階</b>																			
脚立足場	運搬費込	m2	6.57	x	5.00	=	32.85											32.85	
	H=1.8m 並列(1ヶ月)		0.60	x	0.60	=	0.36											0.36	
																		33.21	
床養生	ブルーシート	m2	6.57	x	5.00	=	32.85											32.85	
																		32.85	
竣工時清掃後片付け		m2	6.57	x	5.00	=	32.85											32.85	
																		32.85	
<b>217. 隊舎 6階</b>																			
脚立足場	運搬費込	m2	6.57	x	5.00	=	32.85											32.85	
	H=1.8m 並列(1ヶ月)		0.60	x	0.60	=	0.36											0.36	
																		33.21	
床養生	ブルーシート	m2	6.57	x	5.00	=	32.85											32.85	
																		32.85	
竣工時清掃後片付け		m2	6.57	x	5.00	=	32.85											32.85	
																		32.85	
<b>217. 隊舎 7階</b>																			
脚立足場	運搬費込	m2	6.57	x	5.00	=	32.85											32.85	
	H=1.8m 並列(1ヶ月)		0.60	x	0.60	=	0.36											0.36	
																		33.21	
床養生	ブルーシート	m2	6.57	x	5.00	=	32.85											32.85	
																		32.85	
竣工時清掃後片付け		m2	6.57	x	5.00	=	32.85											32.85	
																		32.85	
<b>218. 屋外便所 1階</b>																			
脚立足場	運搬費込	m2	10.00	x	5.60	=	56.00											56.00	
	H=1.8m 並列(1ヶ月)		-5.00	x	-2.70	=	-13.50											-13.50	
																		42.50	
床養生	ブルーシート	m2	10.00	x	5.60	=	56.00											56.00	
			-5.00	x	-2.70	=	-13.50											-13.50	
																		42.50	
竣工時清掃後片付け		m2	10.00	x	5.60	=	56.00											56.00	
			-5.00	x	-2.70	=	-13.50											-13.50	
																		42.50	
<b>219. 車両整備場 1階</b>																			
脚立足場	運搬費込	m2	5.05	x	3.00	=	15.15											15.15	
	H=1.8m 並列(1ヶ月)		0.91	x	0.91	=	0.83											0.83	

数量算出書(建築)

名 称	摘要	拾														小計	合計	単位	改め計
			0.60	x	0.60			=	0.36							0.36			
			0.60	x	0.60			=	0.36							0.36			
			0.60	x	0.60			=	0.36							0.36	17.06	m2	17.1
床養生	ブルーシート	m2	7.00	x	3.00			=	21.00							21.00	21.00	m2	21.0
竣工時清掃後片付け		m2	7.00	x	3.00			=	21.00							21.00	21.00	m2	21.0
219.車両整備場 2階																			
脚立足場	運搬費込	m2	3.80	x	3.00			=	11.40							11.40			
	H=1.8m 並列(1ヶ月)		5.05	x	3.00			=	15.15							15.15			
			0.60	x	0.60			=	0.36							0.36			
			0.60	x	0.60			=	0.36							0.36			
			0.60	x	0.60			=	0.36							0.36			
			0.60	x	0.60			=	0.36							0.36	27.99	m2	28.0
床養生	ブルーシート	m2	7.00	x	6.00			=	42.00							42.00	42.00	m2	42.0
竣工時清掃後片付け		m2	7.00	x	6.00			=	42.00							42.00	42.00	m2	42.0
222.隊舎(1F)																			
脚立足場	運搬費込	m2	0.91	x	0.91			=	0.83							0.83	0.83	m2	0.8
	H=1.8m 並列(1ヶ月)																		
床養生	ブルーシート	m2	3.27	x	7.05			=	23.05							23.05	23.05	m2	23.1
竣工時清掃後片付け		m2	3.27	x	7.05			=	23.05							23.05	23.05	m2	23.1
222.隊舎 2階																			
脚立足場	運搬費込	m2	3.27	x	7.05			=	23.05							23.05			
	H=1.8m 並列(1ヶ月)		0.60	x	0.60			=	0.36							0.36			
			0.60	x	0.60			=	0.36							0.36	23.77	m2	23.8
床養生	ブルーシート	m2	3.27	x	7.05			=	23.05							23.05	23.05	m2	23.1
竣工時清掃後片付け		m2	3.27	x	7.05			=	23.05							23.05	23.05	m2	23.1
222.隊舎 3階																			
脚立足場	運搬費込	m2	3.27	x	7.05			=	23.05							23.05			
	H=1.8m 並列(1ヶ月)		0.60	x	0.60			=	0.36							0.36			
			0.60	x	0.60			=	0.36							0.36	23.77	m2	23.8
床養生	ブルーシート	m2	3.27	x	7.05			=	23.05							23.05	23.05	m2	23.1

数量算出書(建築)

名 称	摘要	拾										小計	合計	単位	改め計			
竣工時清掃後片付け		m2	3.27	x	7.05			=	23.05						23.05	23.05	m2	23.1
222. 隊舎 4階																		
脚立足場	運搬費込	m2	3.27	x	7.05			=	23.05						23.05			
	H=1.8m 並列(1ヶ月)		0.60	x	0.60			=	0.36						0.36			
			0.60	x	0.60			=	0.36						0.36	23.77	m2	23.8
床養生	ブルーシート	m2	3.27	x	7.05			=	23.05						23.05	23.05	m2	23.1
竣工時清掃後片付け		m2	3.27	x	7.05			=	23.05						23.05	23.05	m2	23.1
222. 隊舎 5階																		
脚立足場	運搬費込	m2	3.27	x	7.05			=	23.05						23.05			
	H=1.8m 並列(1ヶ月)		0.60	x	0.60			=	0.36						0.36			
			0.60	x	0.60			=	0.36						0.36	23.77	m2	23.8
床養生	ブルーシート	m2	3.27	x	7.05			=	23.05						23.05	23.05	m2	23.1
竣工時清掃後片付け		m2	3.27	x	7.05			=	23.05						23.05	23.05	m2	23.1
222. 隊舎 6階																		
脚立足場	運搬費込	m2	5.80	x	7.05			=	40.89						40.89			
	H=1.8m 並列(1ヶ月)		0.60	x	0.60			=	0.36						0.36			
			0.60	x	0.60			=	0.36						0.36	41.61	m2	41.6
床養生	ブルーシート	m2	5.80	x	7.05			=	40.89						40.89	40.89	m2	40.9
竣工時清掃後片付け		m2	5.80	x	7.05			=	40.89						40.89	40.89	m2	40.9
222. 隊舎 7階																		
脚立足場	運搬費込	m2	5.80	x	7.05			=	40.89						40.89			
	H=1.8m 並列(1ヶ月)		0.60	x	0.60			=	0.36						0.36			
			0.60	x	0.60			=	0.36						0.36	41.61	m2	41.6
床養生	ブルーシート	m2	5.80	x	7.05			=	40.89						40.89	40.89	m2	40.9
竣工時清掃後片付け		m2	5.80	x	7.05			=	40.89						40.89	40.89	m2	40.9
222. 隊舎 8階																		
脚立足場	運搬費込	m2	5.80	x	7.05			=	40.89						40.89			
	H=1.8m 並列(1ヶ月)		0.60	x	0.60			=	0.36						0.36			
			0.60	x	0.60			=	0.36						0.36	41.61	m2	41.6
床養生	ブルーシート	m2	5.80	x	7.05			=	40.89						40.89	40.89	m2	40.9









数量算出書(建築)

名 称	摘要	拾										い		小計	合計	単位	改め計			
床 タイル撤去	50角 下地モルタル共	m2	3.00	x	3.80			=	11.40											
			3.00	x	5.00			=	15.00											
			-1.25	x	-1.50			=	-1.88											
								=	24.53	x	0.03	=	0.74							
床 コンクリート撤去	t=150 700*400	カ所	1.00					=	1.00	x	0.04	=	0.04							
床 タイル撤去	50角 下地モルタル共	m2	3.28	x	7.05			=	23.12	x	0.03	=	0.69							
床 コンクリート撤去	t=150 700*400	カ所	1.00					=	1.00	x	0.04	=	0.04							
床 タイル撤去	50角 下地モルタル共	m2	3.28	x	7.05			=	23.12	x	0.03	=	0.69							
床 コンクリート撤去	t=150 700*400	カ所	1.00					=	1.00	x	0.04	=	0.04							
床 タイル撤去	50角 下地モルタル共	m2	3.28	x	7.05			=	23.12	x	0.03	=	0.69							
床 コンクリート撤去	t=150 700*400	カ所	4.00					=	4.00	x	0.04	=	0.16							
床 タイル撤去	50角 下地モルタル共	m2	5.80	x	7.05			=	40.89											
			1.10	x	1.85			=	-2.04											
			0.15	x	1.30			=	-0.20											
			0.15	x	1.30			=	-0.20											
			0.30	x	3.60			=	-1.08											
			0.45	x	0.85			=	-0.38											
					=	37.00	x	0.03	=	1.11										
床 コンクリート撤去	t=150 700*400	カ所	4.00					=	4.00	x	0.04	=	0.16							
床 タイル撤去	50角 下地モルタル共	m2	5.80	x	7.05			=	40.89											
			1.10	x	1.85			=	-2.04											
			0.15	x	1.30			=	-0.20											
			0.15	x	1.30			=	-0.20											
			0.30	x	3.60			=	-1.08											
			0.45	x	0.85			=	-0.38											
					=	37.00	x	0.03	=	1.11										
床 コンクリート撤去	t=150 700*400	カ所	4.00					=	4.00	x	0.04	=	0.16							







数量算出書(建築)

名 称		摘要	拾											小計	合計	単位	改め計	
	天井 化粧石膏ボード	アスベスト含有建材	m2	0.60	x	0.60			=	0.36	x	0.01	=	0.004				0.004
	天井 シーリング石膏ボード撤去	アスベスト含有建材	m2	0.60	x	0.60			=	0.36	x	0.01	=	0.004				0.004
				0.60	x	0.60			=	0.36	x	0.01	=	0.004				0.004
				0.60	x	0.60			=	0.36	x	0.01	=	0.004				0.004
	天井 化粧石膏ボード	アスベスト含有建材	m2	0.60	x	0.60			=	0.36	x	0.01	=	0.004				0.004
	天井 シーリング石膏ボード撤去	アスベスト含有建材	m2	0.60	x	0.60			=	0.36	x	0.01	=	0.004				0.004
				0.60	x	0.60			=	0.36	x	0.01	=	0.004				0.004
				0.60	x	0.60			=	0.36	x	0.01	=	0.004				0.004
	天井 化粧石膏ボード	アスベスト含有建材	m2	0.60	x	0.60			=	0.36	x	0.01	=	0.004				0.004
	天井 シーリング石膏ボード撤去	アスベスト含有建材	m2	0.91	x	0.91			=	0.83	x	0.01	=	0.008				0.008
				0.60	x	0.60			=	0.36	x	0.01	=	0.004				0.004
	天井 化粧石膏ボード	アスベスト含有建材	m2	0.91	x	0.91			=	0.83	x	0.01	=	0.008				0.008
				0.60	x	0.60			=	0.36	x	0.01	=	0.004				0.004
	天井 シーリング石膏ボード撤去	アスベスト含有建材	m2	0.60	x	0.60			=	0.36	x	0.01	=	0.004				0.004
				0.60	x	0.60			=	0.36	x	0.01	=	0.004				0.004
				0.60	x	0.60			=	0.36	x	0.01	=	0.004				0.004
	天井 化粧石膏ボード	アスベスト含有建材	m2	0.60	x	0.60			=	0.36	x	0.01	=	0.004				0.004
	天井 シーリング石膏ボード撤去	アスベスト含有建材	m2	0.91	x	0.91			=	0.83	x	0.01	=	0.008				0.008
	天井 シーリング石膏ボード撤去	アスベスト含有建材	m2	0.91	x	0.91			=	0.83	x	0.01	=	0.008				0.008
	天井 化粧石膏ボード	アスベスト含有建材	m2	0.60	x	0.60			=	0.36	x	0.01	=	0.004				0.004
				0.60	x	0.60			=	0.36	x	0.01	=	0.004				0.004
	天井 シーリング石膏ボード撤去	アスベスト含有建材	m2	0.91	x	0.91			=	0.83	x	0.01	=	0.008				0.008
	天井 化粧石膏ボード	アスベスト含有建材	m2	0.60	x	0.60			=	0.36	x	0.01	=	0.004				0.004
				0.60	x	0.60			=	0.36	x	0.01	=	0.004				0.004
	天井 シーリング石膏ボード撤去	アスベスト含有建材	m2	0.60	x	0.60			=	0.36	x	0.01	=	0.004				0.004
	天井 化粧石膏ボード	アスベスト含有建材	m2	0.60	x	0.60			=	0.36	x	0.01	=	0.004				0.004
				0.60	x	0.60			=	0.36	x	0.01	=	0.004				0.004
	天井 シーリング石膏ボード撤去	アスベスト含有建材	m2	0.91	x	4.55			=	4.14	x	0.01	=	0.041				0.041
	天井 化粧石膏ボード	アスベスト含有建材	m2	0.60	x	0.60			=	0.36	x	0.01	=	0.004				0.004
				0.60	x	0.60			=	0.36	x	0.01	=	0.004				0.004
	天井 シーリング石膏ボード撤去	アスベスト含有建材	m2	0.91	x	4.55			=	4.14	x	0.01	=	0.041				0.041
	天井 化粧石膏ボード	アスベスト含有建材	m2	0.60	x	0.60			=	0.36	x	0.01	=	0.004				0.004
				0.60	x	0.60			=	0.36	x	0.01	=	0.004				0.004
	天井 シーリング石膏ボード撤去	アスベスト含有建材	m2	0.60	x	0.60			=	0.36	x	0.01	=	0.004				0.004
				0.60	x	0.60			=	0.36	x	0.01	=	0.004				0.004
	天井 化粧石膏ボード	アスベスト含有建材	m2	0.60	x	0.60			=	0.36	x	0.01	=	0.004				0.004

































材料積算表

工事名称： 久留米駐屯地便所改修設計(電気設備)

工事種別： 16. (222) 隊舎

1/2

名 称		2F平面		2F平詳		3F平面		3F平詳		4F平面		4F平詳		5F平面		5F平詳		6F平面		6F平詳		集 計	
工 種	規格・寸法・工法	ヨコ	タテ	ヨコ	タテ	ヨコ	タテ	ヨコ	タテ	ヨコ	タテ	ヨコ	タテ	ヨコ	タテ	ヨコ	タテ	ヨコ	タテ	ヨコ	タテ	小計	採用数量
ケーブル	EM-EEF 2.0-3C コロガシ	6.5	2.0	3.5	1.9	6.5	2.0	3.5	1.9	6.5	2.0	3.5	1.9	6.5	2.0	12.0	3.8	18.0	4.0	17.5	7.6	113.1	
1種金属線び	MM A				1.9				1.9				1.9				3.8				7.6	17.1	
1種金属線び	MM A コーナボックス			1.0				1.0				1.0			2.0					4.0		9.0	
1種金属線び	MM A スイッチボックス			1.0				1.0				1.0			2.0					4.0		9.0	
電線管	EP 25mm インベイ		1.0				1.0				1.0				1.0							4.0	
電線管	EP 31mm インベイ																		1.0			1.0	
アウトレットボックス	OB 中浅 C付 樹脂製														1.0					2.0		3.0	
埋込コンセント	2P15A, EET付 金属P共			1.0				1.0				1.0			2.0					4.0		9.0	
既設電灯盤改造	2L-3	1.0																				1.0	
既設電灯盤改造	3L-3					1.0																1.0	
既設電灯盤改造	4L-3									1.0												1.0	
既設電灯盤改造	5L-3													1.0								1.0	
既設電灯盤改造	6L-3																	1.0				1.0	
貫通補修費	50Φ	1.0				1.0				1.0				1.0				1.0				5.0	
区画貫通処理材	31Φ	1.0				1.0				1.0				1.0				1.0				5.0	
名 称		7F平面		7F平詳		8F平面		8F平詳														集 計	
工 種	規格・寸法・工法	ヨコ	タテ	ヨコ	タテ	ヨコ	タテ	ヨコ	タテ	ヨコ	タテ	ヨコ	タテ	ヨコ	タテ	ヨコ	タテ	ヨコ	タテ	ヨコ	タテ	小計	採用数量
ケーブル	EM-EEF 2.0-3C コロガシ	18.0	4.0	17.5	7.6	18.0	4.0	17.5	7.6													94.2	
1種金属線び	MM A				7.6				7.6													15.2	
1種金属線び	MM A コーナボックス			4.0				4.0														8.0	
1種金属線び	MM A スイッチボックス			4.0				4.0														8.0	
電線管	EP 25mm インベイ																						
電線管	EP 31mm インベイ		1.0				1.0															2.0	
アウトレットボックス	OB 中浅 C付 樹脂製			2.0				2.0														4.0	
埋込コンセント	2P15A, EET付 金属P共			4.0				4.0														8.0	
既設電灯盤改造	7L-3	1.0																				1.0	
既設電灯盤改造	8L-3					1.0																1.0	
貫通補修費	50Φ	1.0				1.0																2.0	
区画貫通処理材	31Φ	1.0				1.0																2.0	





「便所改修設計」

機械設備工事 数量算出書

作成：令和 7年 10月 日